



Rabbi Akiva's Sukkah



Dated: 23 August 2026
No copyright is sought.

An online working version is at: <https://sukkah.org>

According to the Gemara, the Rabbanan maintain that a sukkah is a דירת עראי. There are many contextual indications of this within Masechet Sukkah. However, one of the most pointed statements regarding this is in Yoma 10b where it directly states: ורבנן לטעמייהו, דאמרי: סוכה דירת עראי בעינן. This being the case, how did the Rabbanan maintain their opinion that a sukkah is a דירת עראי in opposition to Rabbi Yehuda, when Rabbi Yehuda brings a מעשה on Sukkah 2b regarding Queen Helene's sukkah that was over 20 amos high and the Elders were silent, as the Baraisa states: פסולה — סוכה שהיא גבוהה למעלה מעשרים אמה. אמר רבי יהודה: מעשה בהילני המלכה בלוד שהיתה סוכתה ורבי יהודה מכשיר עד ארבעים וחמשים אמה. והיו זקנים נכנסין ויוצאין לשם ולא אמרו לה דבר גבוהה מעשרים אמה.

Therefore, if the Rabbanan who hold that a sukkah is a דירת עראי are assumed to be the opinion of Tanna Kamma of Masechet Sukkah, Mishna 2a, which states that a sukkah above 20 amos is invalid, what logical defense did they employ to avoid refutation by Rabbi Yehuda's Baraisa when Queen Helene's sukkah was over 20 amos high and the Elders were silent?

This d'var Torah attempts to provide an answer to the above question by:

- Illustrating Rabbi Yehuda's opinion of קבע in Mishna 2a and on daf 7b, as meaning that a sukkah can be higher than 20 amos in height or greater than 4×4 amos in length and width, in accordance with the Meiri in alignment with the Baraisa on 3b.
- Explaining how the three dictums in the name of Rav on 2b regarding the dispute between the Tanna Kamma and Rabbi Yehuda in a sukkah above 20 amos are not contradictions but represent multiple opinions of Tannaim which were accurately transmitted by Rav to R' Yoshiyah, Rav Huna, and Rav Chanan bar Rabbah.
- Explaining the source and reason behind Rav Chanan bar Rabbah's dictum in the name of Rav on 2b that states that the dispute with Rabbi Yehuda in a sukkah above 20 amos is at ראשו ורובו ושולחנו.
- Explaining how the seemingly abrupt transition from the Baraisa of Queen Helene's sukkah to Rav Shmuel bar Yitzchak stating the halacha for a minimum size sukkah are not separate topics but related.
- Redefining the concept of a דירת עראי.
- Extrapolating a more complete understanding from the language of the Gemara.

Introduction

This work approaches the Gemara under two methodological commitments. The first commitment is to give interpretive priority to the Talmud's own language and structure. When the Gemara's own words can carry a resolution, that resolution is preferred.

The second commitment emerged in the course of working with this sugya, and appears to be built into the design of the Gemara itself — an approach that makes the sugya's architecture intelligible. It is the conviction that a sugya is best read as a sustained argument in which each component reshapes the interpretation of those that precede and prepares the interpretation of those that follow. Each Mishna, Baraisa, halachic dictum, and conspicuous silence is treated as a deliberate structural choice carrying interpretive weight. The proper understanding of any given detail is provisional until the whole has unfolded, and the whole is itself clarified and revised by each new detail. This is the stitchwork by which the Gemara reveals the front of the tapestry.

A note on peshat and psak. This analysis is peshat — a reconstruction of what each Tanna holds and of how the sugya coheres as a single argument — and not a ruling in halacha lema'aseh. Where the reconstruction yields a consequence that departs from the codified law — that the Rabbanan's own conception of a דירת עראי would tolerate a narrow sukkah above twenty amos, or that their minimum size sukkah is ראשו ורובו, beneath the accepted שבעה על שבעה טפחים — that consequence describes the logic of the sugya, not what one may build. In practice the halacha is as the poskim have fixed it: a sukkah above twenty amos is פסולה, and its minimum measure is seven-by-seven tefachim (Shulchan Aruch, Orach Chaim 633:1 and 634:1). The categorical form of that ruling is itself the Mishnah's פסיק ותני — the very simplification this work sets out to read beneath — so that the codified law and the fuller conception recovered here are each true in their own register. To reconstruct a Tannaitic position for the sake of understanding it, even one the halacha did not follow, is the ordinary labor of limud; the distance between the logic of a shitah and the maskana lehalacha is to be expected, and not a difficulty to be explained away.

Editorial Note: AI was used for summarizing chapters, translating, editing, and proofing this text.

Table of Contents

The Gemara

Masechet Sukkah daf 2a through 3b.	10
------------------------------------	----

Chapter 1 - Questions and Answers on Masechet Sukkah

1. What is the overall structural approach of the Gemara in seeking to understand the individual statements of Masechet Sukkah, Mishna 2a?	17
2. What is being taught by the Gemara when it begins by asking what is unique about a sukkah whose s'chach is higher than 20 amos compared to a mavoi whose korah is higher than 20 amos?	18
3. What is the definition of a דירת עראי?	21
4. Does Rabbi Yehuda allow a sukkah to be built at 20 amos or less in height?	26
5. Rabbi Yehuda allows a sukkah to be higher than 20 amos because he holds that a sukkah is a דירת קבע, but what is his קבע requirement without which a sukkah would be invalid if he at the same time holds that a sukkah can also be built at 20 amos or lower in height?	28
6. Why does Rav Huna in the name of Rav state that the dispute between the Tanna Kamma and Rabbi Yehuda in a sukkah above 20 amos is at exactly 4×4 amos rather than 4×4 amos and less?	31

7. In the name of Rav, Rav Huna and Rav Chanan bar Rabbah argue over a matter of length on 2b, but what is the source of their dispute?	33
8. Why does the Gemara state on 2b that Rav Chanan bar Rabbah's opinion in the name of Rav is not like one of the three Amoraim?	36
9. If Rav Chanan bar Rabbah agrees with R' Yoshiyah that the source for the 20 amos height limitation of sukkah is למען ידעו, why does the Gemara on 2b state that R' Yoshiyah disagrees with Rav Chanan bar Rabbah because he gives a measurement of length?	37
10. How does Rav Huna and Rav Chanan bar Rabbah's opinions accomplish equal or greater shade at the floor of the sukkah in accordance with Gemara 22b and Mishna 2a in a sukkah above 20 amos in height?	39
11. What is Rabbi Yehuda's opinion regarding the minimum amount of shade time when he allows a sukkah to be as high as 40 or 50 amos?	40
12. Why is there no transition from Rabbi Yehuda's Baraisa of Queen Helene's sukkah on 3a to Rav Shmuel bar Yitzchak stating the halacha of a minimum size sukkah?	41
13. What is the meaning and significance of Rav Nachman bar Yitzchak's challenge to Rav Shmuel bar Yitzchak?	44
14. How do we know that the Gemara concluded that Beis Shammai and Beis Hillel are in fact arguing in a small sukkah over a דאורייתא requirement as to whether a sukkah is a דירת עראי or דירת קבע?	45
15. What is the source of the dispute between Beis Shammai and Beis Hillel regarding the minimum size of a sukkah?	47

16. Since the Gemara proves that Beis Shammai and Beis Hillel do argue in a small sukkah over a דאורייתא, and not like Rav Nachman bar Yitzchak suggested over a דרבנן, what then is the driving essence of Beis Shammai and Beis Hillel's argument in a large sukkah at the conclusion of the Gemara's discussion on 3a?
..... 49
17. After discussing the dispute between Beis Shammai and Beis Hillel, why does the Gemara ask the reader on 3a to identify the author of the Baraisa on 3b regarding a house that is less than 4×4 amos?
..... 51
18. What are the logical consequences of the Gemara revealing on 3b that the Rabbanan maintain that a sukkah is a דירת עראי in accordance with Beis Hillel as described on 3a, when the Gemara interprets the Baraisa regarding a house that is less than 4×4 amos according to the Rabbanan's perspective?
..... 54

A Preemptive Reply

19. How should we understand the solution offered by the תוספות רי"ד and ריטבא who conceptualize Queen Helene's sukkah as being comprised of two sections with differing heights to explain how the Rabbanan maintained their opinion that a sukkah is a דירת עראי?
..... 60
20. If the Rabbanan who hold that a sukkah is a דירת עראי allow a sukkah to be above 20 amos why does the Gemara on 3b discuss the need to reduce its size with various materials implying that a sukkah above 20 amos is invalid?
..... 65
21. If the Rabbanan who hold that a sukkah is a דירת עראי permit a sukkah to be built above 20 amos, why does the Gemara state on 4a that a sukkah whose s'chach provides shade from above 20 amos is invalid?
..... 66

22. If so, what is the dispute between the Tanna Kamma and Rabbi Yehuda regarding a sukkah atop another sukkah in Mishna 9b?
..... 67
23. If the Elders who visited Queen Helene permit a sukkah to be above 20 amos when less than 4x4 amos in area, why does the Tanna Kamma of the Mishna 2a state categorically that a sukkah above 20 amos is invalid?
..... 70
- (פשוט)

The Gemara

The following pages present the text of Masechet Sukkah daf 2a through 3b. This is the passage upon which the d'var Torah is primarily built. The reader is encouraged to study this sugya carefully before proceeding, as each question and answer in Chapter 1 follows the order and language of the Gemara as it appears here for convenience.

סוכה פרק ראשון סוכה

לא נזכרה אלא לקטניות שבה - מה שדחק בקוממס לרב חזק
בזר רבה מה ראה לרבי יהודה לא חי אפשר לנכנס בנים
בשכניהם פסחים לא פירכא היא דלמלא ארוכה טובא אבל לא היסה
תתיהם "שכניהם פסחים" ובניה בלחיו ארוך היו יתבי :

דאמר לך מני ב"ש היא ולא

חזו חזיה ט' - בסדר

רב עמרם פסק בשעה מקצות

הלכה כב"ש חזא האי דמוסא לריכה

שחזא מחזקת רלשו ורבו ופולחט

ואידך במנחות פרק ההכלת (דף מ)

(תס) גבי סדן בלית ב"ש פסקין

וביה מחזיקין עוד לשם כמה חזקין

הא טעון ב"ש אמר ר' ובזא"ג

עוד הסם כמה חזא משולח ביה

שחזא לומר ר' ובזא"ג בכל הני

טבדי כב"ש ואידך במסכת גרסות

פרק אל דבריה (דף וזא) כב"ש

מכבדן אלא הכים וחזא טעלין לידים

ואמרין בגמ' בטליה פירקין הלכה

כב"ש בר מהך עוד הסם בסוף

פירקא גבי מי שאל "טענה ולא בירך

הא דמיתיה בגמרא שובא דרבה בר בר

הא דלמסח יונה דרבהא יחד חלמדי

דעבד כב"ש ואשכח ארבעין ואידך

חלמדי דעבד כב"ש ואשכח ארבע

וקאל קשה הא קאמר הסם בטליה

פירקין הלכה כב"ש בר מהך ושחזא

מסוס דב"ש נמי ועוד דלמחזילה

מיהא טבדין כב"ש חזו מה שפסק

בזך דהכא כב"ש אין להקשות מהא

דלמירין פ"ק דברכות (דף יא) דאמר

רב יוסף עשה דבריה ב"ש לא טעם

ולאכלס ומיתיה ליה מהאי מילתא

דמוסא מעשה דבריה יומן חזירי

שחזא הלש זקי ב"ש וחזקי ב"ש

לבקרו ומלחיה ססיה יוסב רלשו

ורבו כב"ש ופולחט בתוך הבית

אמר לו זקי ב"ש אלץ בית טב

כל יומך לך קיימת מלות טוב

ימך ומספקת הסם פלוגתא כב"ש

יומן חזירי והיא פלוגתא כב"ש

גדולה דמספקת דבריה פלוגתא

כב"ש הלכה כב"ש אבל האל כב"ש

קטנה ונכח הלכה כב"ש מיה

שמעתי והסם דמיה הכי דיק מניה

דעשה כב"ש לא עשה ולא כלום

דרחיה דמיתיה בעשה כב"ש מירי

ועוד וזי לרך רלוי על זה היכא

הלכה כב"ש שחזא עשה כב"ש לא

עשה ולא כלום וזי דלמירין הסם

לחזי"י יחזא דב"ש מתעורר מדברק

וב"ש מקמי לה דלמיריחא ולא

גזיקין חס עשה דבריה ב"ש לא יחזא

די מעבד חזי דלמיריחא דלמיריחא

לג"ס יחזא דיקו אשיתא דמללחא

דגזיק שחזא ימך חזר שחזא וקאמר

לא קיימת מלות טוב מיריחא דלמיריחא

דלמיריחא לא קייס ומדבית שחזא

שחזא לב"ש ב"ת שחזא זו ד'

אחש - בירושלמי תביב שחזא טוב

למפער והטור מן הבית ליכנס וזי ועוד הוא ליה למפער

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

לענין פסח בית אל של כעבור החורשים :

מסוס אירא - רוח שחזא שולט בה חזי : חס : אלא למ"ד בקטנה
פלגי - אבל בגדולה אשלו רבן שחזא : וזי דרבה של מלכה - והאל
נעדרתיה ומתרחס חסבים עשה : לקטניות שבה - סוכה גדולה
לכני מסוכה' וקטניות קטנה בחובה לנעשות והיא בקטניות יתבא
ואלפי דפסולה לא ארבעה לן דלמיריחא

שחזא מן הסוכה : ורבי יהודה סבר

ט' - וזיח לרב חזן דמוק פלוגתא

בשחזא מחזקת אלא כדי רלשו ורבו

ופולחט הכא כיון דבניה גבה היא

לה גדולה ומדו בה רבן וחזא רלוי

של רבי יהודה יל דלמיריחא בסך

הסוכה הגדולה היסה ובניה על

השולק היו ופסקין רלשו ורבו ולא

כמסוכין ון ולא מקשיין וזי מלחא

חזא לרב חזן קשיו וחזא מירחא

לרב האל הא וכן פיקר דשחזא

רלשו ורבו אמרין לקמן דלש אלא

ו' מסוסין וחזא חזא לשבעה בנים

בשבעה פסחים : כב"ש - דלי כב"ש

לא כפי שחזא דלמיריחא בסך היסן

(דף מה) : ודיקא נמי גרסין ודיקא

נמי דלמיריחא בגדולה פלגי וזי וזי

על הפסח מחזקת רלשו ורבו ופולחט

ופולחט פלגי גבו בנים : מדקמי -

גבי פלוגתא מן שחזא ולא חזירי

בשחזא דמוסא : וזי חזא -

דבשחזא דמוסא פלגי ליתא : סוכה

המחזקת רלשו ורבו ופולחט כשה

ושחזא מחזקת אלא כדי רלשו ורבו

ב"ש פוסלין ט' : אמר מר שחזא

דיקא נמי : דקטנה פלגי ובשחזא

דמוסא : טעם מפרש שחזא לקמן :

אחש נחלס - אלא שחזא לעולם

ויחזא ביובל חס לא נחל כשאר קרקע

כלל בנין : משוריי החלחלה - מן :

האש חזר כנה בית חדש וגו' (דברים כ) :

ואין מערבין ט' - דרך

בניהם לית פסחין חזא וזכר

בנים פסחים חזא אחת וזי וזי

דך חזר לרשית הדבס נחל חזא

רשית נחל והבנים כל אחד מיוחד

לנעלו ואחרי חזמים אין מוזילין

דמיריחא לרשית נחל פירוב שחזא

כל הרשויות ביהם רשית אחס

וחזקת ליתן כל בית ובית שחזא

פס וזלן ככל אחד ומיתין אחס

כחזקת דמיריחא ונעשים טעם כחזא

דרין נחשו בית וכל בניהם דירה

אחז ואשחזקת האל דבית שחזא

ז' פל ד' אין לרך ליתן חס הפס :

ואן משחזקת ט' : שחזקת חזמים

על כל חזר הפסחה למזי כדרך

שחזקת פירוב לבני חזא שחזא

טענה בשחזא חס בית קמן זה

פסח חזא כעמדי ואן בית

אחז פסח לה אין משחזקת ט

אין נחשו ליתן בשחזא : ואן

מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

ואין מיתין ט פירוב - חזא חזא

פ"ה אבד רב
חזא

בכמה יא.
לקמן ט כה
פירוק יא

[קמן] יא
פירוק יא
פסח יא

[אלה] שחזא כב"ש

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

[ואין] רבי חזא

Chapter 1

Questions and Answers on Masechet Sukkah

The Gemara's analysis of the גיטא of Mishna 2a unfolds as a single sustained argument from Sukkah 2a through 4b. What appears at first glance to be a series of discrete topics — the comparison to a mavoi, the three Amoraic sources for the 20 amos height limitation, the dicta in the name of Rav, Queen Helene's sukkah, the dispute between Beis Shammai and Beis Hillel, and the Baraisa regarding houses — is in truth one continuous thread of reasoning. The Gemara is methodically building toward a complete understanding of how the dimensions of height, length, and width determine whether a sukkah is a דירת עראי or a דירת קבע, and how the Rabbanan maintained their opinion that a sukkah is a דירת עראי in the face of Rabbi Yehuda's proof from Queen Helene's sukkah. The following questions and answers trace this thread from beginning to end, following the order in which the Gemara itself presents its reasoning.

The Gemara begins examining Mishna 2a **by comparing the רישא** of our Mishna to the רישא of the Mishna in Eruvin 2a. As such, a continuous thread of logical thought unfolds from Sukkah 2a through 4b to methodically proceed through all the factors that affect the limitations and calculations of the height of s'chach from the floor of a sukkah.

סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות

סוכה פרק ראשון

סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות

סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות



סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות

סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות

סוכה

סוכה - חג יום טוב
החג נמשך 7 ימים
הוא חג של שמחה
והוא חג של תורה
והוא חג של מצוות

17 | Page

In quoting **only the רישא** of the Mishna in Eruvin 2a, the Gemara asks two different questions on Sukkah 2a: מאי שנא גבי סוכה דתני פסולה. ומאי שנא גבי מבוי דתני תקנתא. Why is one question insufficient that the Gemara needed to ask both of these questions?

[illegible]

18 | Page

After accepting the uniqueness of a sukkah which allows us to state פסולה, the Gemara then proceeds to address the second question regarding the uniqueness of a מבוּי that allows us to **exclusively state a תקנתא**. The Gemara does this by way of first suggesting that perhaps a מבוּי is not unique because a person could state a תקנתא for a דאורייתא and say in regard to a sukkah ימעט if the sukkah's s'chach is higher than 20 amos, as the Gemara states: ואיבעית אימא בדאורייתא נמי תני תקנתא.

However, the Gemara explains that even though in general a תקנתא could be given for a דאורייתא, in the specific case of a sukkah whose s'chach is higher than 20 amos, there are numerous details regarding **the lowering of the s'chach** of a sukkah that prevents a person from simply stating ימעט as a remedy, מיהו סוכה דנפיש מילתה. Therefore, the answer to the second question is that a mavoi is unique from a sukkah in that it can exclusively state a תקנתא regarding its korah which is over 20 amos, because the details involved are not numerous, מבוּי דלא נפיש מיליה. Consequently, the korah simply needs to be lowered, ימעט. **This cannot be stated by a sukkah because the details for lowering s'chach are numerous.**

In order to explain how and why the details for lowering s'chach are numerous, the Gemara proceeds with providing the necessary context by first listing the three opinions of the Amoraim regarding the possible sources for 20 amos height limitation of a sukkah. Then it highlights multiple corresponding dicta in the name of Rav on 2b, each of which would consequently impact the requirements for lowering s'chach in different ways. For instance, R' Yoshiyah said in the name of Rav, that the dispute between the Tanna Kamma and Rabbi Yehuda is where the walls do not reach the s'chach. Therefore, according to this opinion a sukkah above twenty amos whose walls reach the s'chach is not פסולה and it need not be lowered at all. Whereas a sukkah whose walls do not reach the s'chach must be lowered to 20 amos or below. However, according to Rav Huna in the name of Rav, the dispute is at exactly 4×4 amos, which establishes a required shade ratio of 1:5 (length to height). Therefore, if the sukkah is 5×5 amos and the s'chach is at 26 amos in height, it needs to be lowered only 1 amah and not necessarily to 20 amos. In addition, according to this opinion a sukkah of 3×3 amos that is over 20 amos in height, even if it were lowered to 16 amos it would still be פסולה. Next, according to Rav Chanan bar Rabbah the dispute is at ראשו ורובו ושולחנו. And as it shall be explained further below, if the sukkah is exactly ראשו ורובו ושולחנו then the sukkah must be lowered to 20 amos or below. However, if the sukkah were larger than ראשו ורובו ושולחנו, depending on its length and width it may or may not need to be lowered.

In addition to understanding the structure and logical flow of the Gemara in this straightforward manner, a proof for this approach to the Gemara can be found in the words of Chazal who stated on 2a, מיהו סוכה דנפיש מיליה. Do not read דנפיש מילתה. Chazal precisely indicated the intent of their words by using the masculine form to ensure that the reader understood that the entire conversation was specifically regarding the numerous

סוכה פרק ראשון סוכה

סוכה - ורבי יהודה מכשיר - בגמרא מפרש פלוגתייהו: ושאלה גבוהה עשרה - בגמרא מפרש עשרה: שלש דפנות - נמי בגמרא יליף לה: ושאלה מרובה מלחלה - המועט במל ברוב והכי הוא כמו שאש ועל שם הסך קרויה סוכה: **גמ'** מבי שהוא גבוה - מבי שהוא סביב משלש תורה אור

לדנין ורלא פתוח לרשות הרבים והצירות הפתוחות לו ויוללות וזכאות לרשות הרבים הרי הוא רשות היחיד לבני חצירות ואסרו חכמים להאיל משאיתו לרשות הציר בלא עירוב שהצירות כל אחת רשות לעצמה והציר רשות לטול והצירות בו שיתוף להחזיק כל הצירות בפתח או בזין ולהניח שיתוף בלחם מן הצירות ולפי שאין לו מחלה רביעית וקרב לא להיות דומה לרשות הרבים הריש הכר בדלא הפתוח לרשות הרבים או לו זקף או קורה ומנהל לטול ואם גבוה הקורה מעשרים אמה: ימעט - ויפיל: איש לרץ - והסח מפרש עמח: סוכה מדאורייתא - דעשרים אמה דילה ילפין מדאורייתא וקורט ששנים התשעה חצורה ששורה משי: הני פסול - שיי למיחוי כהן לטול פסול למחל מבי עשית כחורה וכהלה: מבי - דטליה מהדרינן מדאורייתא מבי ליה כהל מלחח ואש לרץ לקורה זו אלא מדמני: הני הקנא - דלא שייך למחוי כה לטול פסול דמחל

סוכה - מאי שאל גבי סוכה דתני פסולה ומאי שאל גבי מחוי דתני הקנא - והא דלא פריך מחי שאל גבי דתני פסולה וקנא דתני פריך לטול העול [לפני דף גבי]: וא שאל ענינו מדוכין מעלי פסול ואם ימעטן כשר דלא פריך אלא מסיבה ומבי שריש שיה לענין גבוה ושניה לטון משנהו ועוד דגבי הכס אלאקדן למיחוי הקנא דמבי אלאקדן כיון *נדחלו בפסול דו לית ליה הקנא:

דאורייתא הני פסול - דלי הוה הני ימעט חייבין דילמא טבי אריס לומר ימעט לכהילה ודשבר כשרה ודיקדק בלשון דלמא אחי ליה חסירה לדאורייתא וקני פסולה אפי' דלא הוי לישנא מעליא כמו ימעט אבל בחבוי דרבנן לא חייס והנא ימעט שהוא לישנא מעליא דשכחן בריש פסחים (דף יג) שקים הכסוב כמה חצירות שלא להאיל דבר מנוה משי ובקושרים לא פריך כן א' נמי שי לומר דלפון ימעט פתח חצורה דרבנן כעלמא ופסולה משמע דאורייתא ובפרק כמה מליקין (גמ' דף כג) דלמרינן כר חטטה שהיהה למעלה מעשרים אמה פסולה כסוכה וכמבי אלא דמני כסוכה נקט נמי גבי הני פסול איכ

אי הוה הני ימעט הוה משמע כמות שהיה מדלקת ושיעלה או חטט למחל דלמא דולקת שושא מנהאפי' למחל המנה שושא מעלי חטטין דהיהה

סוכה - מאי שאל גבי סוכה דתני פסולה ומאי שאל גבי מחוי דתני הקנא - והא דלא פריך מחי שאל גבי דתני פסולה וקנא דתני פריך לטול העול [לפני דף גבי]: וא שאל ענינו מדוכין מעלי פסול ואם ימעטן כשר דלא פריך אלא מסיבה ומבי שריש שיה לענין גבוה ושניה לטון משנהו ועוד דגבי הכס אלאקדן למיחוי הקנא דמבי אלאקדן כיון *נדחלו בפסול דו לית ליה הקנא:


דאורייתא הני פסול - דלי הוה הני ימעט חייבין דילמא טבי אריס לומר ימעט לכהילה ודשבר כשרה ודיקדק בלשון דלמא אחי ליה חסירה לדאורייתא וקני פסולה אפי' דלא הוי לישנא מעליא כמו ימעט אבל בחבוי דרבנן לא חייס והנא ימעט שהוא לישנא מעליא דשכחן בריש פסחים (דף יג) שקים הכסוב כמה חצירות שלא להאיל דבר מנוה משי ובקושרים לא פריך כן א' נמי שי לומר דלפון ימעט פתח חצורה דרבנן כעלמא ופסולה משמע דאורייתא ובפרק כמה מליקין (גמ' דף כג) דלמרינן כר חטטה שהיהה למעלה מעשרים אמה פסולה כסוכה וכמבי אלא דמני כסוכה נקט נמי גבי הני פסול איכ

אי הוה הני ימעט הוה משמע כמות שהיה מדלקת ושיעלה או חטט למחל דלמא דולקת שושא מנהאפי' למחל המנה שושא מעלי חטטין דהיהה

Furthermore, the Gemara's use of the word סוכה to refer to the סכך can be seen in the statements of the three Amoraim that immediately follow. In each case, the word סוכה can only be understood as referring to the סכך. Take for example, Rabbi Zeira's statement: 'Up to 20 amos, a person sits in the shade of the sukkah; higher than 20 amos, a person sits in the shade of the walls.' Here, the 'shade of the sukkah' is clearly contrasted with the shade of the walls — demonstrating that סוכה in this context means the סכך specifically.

(End.)

makeup or lack of sturdiness in construction does not matter at all. If a דירת עראי occupies the abstract dimension of קבע above 20 amos, it would actually be a דירת קבע and not as Abaye would have thought, a דירת עראי. Therefore, a materially weak or loosely constructed sukkah above 20 amos is invalid. Just as conversely a sukkah made with מחיצות של ברזל is actually a דירת עראי and not a דירת קבע when it occupies the dimensional space of 20 amos or less.



And even though Rashi departs from the plain sense of Rava's words and understands differently than the Bach in stating that it is impossible to build a דירת עראי above 20 amos due to a connection to its material construct, he still concludes in his commentary on Gemara 2b that Rabbah and Rabbi Zeira did not agree with Rava's source for the 20 amos height limitation of a sukkah because they did not want to learn out from the words שבעת ימים an abstract measurement regarding the concept of temporariness and permanent. Instead, they felt that if the words שבעת ימים could be interpreted to mean that a sukkah should be built in some sort of temporary fashion, it would have to be understood as Abaye did in the terms of the material construct of the sukkah.

סוכה פרק ראשון סוכה


סבורת
השם

סלה - הגך אמוראי : כרבה לא אמרי - דילין מלמען ידשו : הסא - לאו בידיעה דישבת סוכה קא אמר אללא בדיעות דורות הבאין היקף סוכה טעמי כבוד הכנסה לאבות : לימות המשיח - אותם סוכות יהיו לכל לשונם ולמסמור אבל סוכה מטה אינה לכל : סוכה - דאין שם סוכה אללא העשויה לכל דהיא דימות המשיח משום דעשויה לכל קרייה סוכה : משום קשיא דאביי - דעשה מחצית של כרכל ושיטרא לא משמע להו האיל וקרא לאו חוקא ערף נקט לא ילפינן מיניה שיטרא : כמאן - מהגך אמוראי דלעיל אולא כך ס' : מחלקת - דר' יהודה ורבנן : משלט שלטא, ביה עינא - דרך דפסת

כרבי וירא לא אמרי - הא דלא קאמר משום קשיא דאביי כדקאמר על רבא משום דרבי וירא שני לאביי שפיר : **וכיון** דדפסת מנישת לסך משלט שלטא ביה עינא - ולא דמי לגר חטכה וקורא מטי דלא משיב היכר למעלה מעשרים אע"פ שהקריה על גבי כפלים דהאם קריה קפח לא שליט בה עינא כעז כסוכה דרבה סוכא : **יש** כה ויתר מלרבע אמות אפילו למעלה מעשרים כשירה - לבסוף מסיק דרב הוגא סבר מיראשו ורובו ושלטא עד ד' אמות פליגי ויתר מד' אמות כשירה ותימה וכו' נקטיר ברחבה משה יתר מד' אמות אם יתה גבוה מעשרים

דענין סוכות דהאם קאמר משום קשיא דאביי כדקאמר על רבא משום דרבי וירא שני לאביי שפיר : **וכיון** דדפסת מנישת לסך משלט שלטא ביה עינא - ולא דמי לגר חטכה וקורא מטי דלא משיב היכר למעלה מעשרים אע"פ שהקריה על גבי כפלים דהאם קריה קפח לא שליט בה עינא כעז כסוכה דרבה סוכא : **יש** כה ויתר מלרבע אמות אפילו למעלה מעשרים כשירה - לבסוף מסיק דרב הוגא סבר מיראשו ורובו ושלטא עד ד' אמות פליגי ויתר מד' אמות כשירה ותימה וכו' נקטיר ברחבה משה יתר מד' אמות אם יתה גבוה מעשרים

Another proof that the definition of a דירת עראי is not determined by the materials used but is an abstract range determined as 20 amos or less can be learned from Gemara 7b where Rabbi Yehuda is listed as one of eight Tannaim that hold that a sukkah is a דירת קבע on the basis that he validates a sukkah above 20 amos in height. From this we find a proof for Rava's understanding that a sukkah which is built at 20 amos or lower in height is in the dimensional range of what is considered a דירת עראי.



The diagram is a large rectangle divided vertically by a dashed line. The left half is white and labeled 'Temporary (עראי)' with the text 'Building Range for Length & Width' below it. The right half is light blue and labeled 'Permanent (קבע)' with the text 'Building Range for Length & Width' below it. At the bottom center, below the dashed line, is the text '4X4' and 'אמה' (Amah).

[illegible]

25 | Page

Yes, as he agrees with Mishna 2a that states: **ושאינה גבוהה עשרה טפחים**. Therefore, a sukkah that is built 10 tefachim or higher is valid.

[illegible]

Also, another proof is where Gemara 23a cites a Baraisa that states: עשאה לבהמה דופן לסוכה — רבי מאיר פוסל ורבי יהודה מכשיר. Regarding this Baraisa, Abaye understands that R' Meir invalidates the use of an animal as a sukkah wall out of concern that it might die, whereas Rabbi Yehuda validates it. The Gemara explains their dispute as where the animal is of average size and its top is within 3 tefachim from the s'chach, which qualifies the sukkah as having the required minimum 10 tefachim in height for a valid sukkah. From here we see that the Gemara understands that Rabbi Yehuda permits a sukkah to be built at 20 amos or lower in height.

Rebbi Yehuda allows a sukkah to be higher than 20 amos because he holds that a sukkah is a קבע דירת, but what is his קבע requirement without which a sukkah would be invalid if he at the same time holds that a sukkah can also be built at 20 amos or lower in height?

The Gemara on 7b states: אמר אביי רבי ור' יאשיה ורבי יהודה ורבי שמעון ורבן גמליאל ובית שמאי. Each one of the Tannaim listed holds that a sukkah needs a particular aspect of קבע in order for a sukkah to be valid. However, if Rebbi Yehuda simply allows a sukkah to be either above 20 amos in height, where it would be a דירת עראי, or 20 amos or lower where it would be דירת קבע, he would not belong on this list of Tannaim that maintain that a sukkah must be a קבע בעינן.


Therefore, in accordance with the Meiri commenting on Gemara 2a, Rebbi Yehuda's קבע requirement of a sukkah can be satisfied either on the basis of the dimension of height or on the basis of the dimension of length and width at 4×4 amos.

The Meiri explains each dimension of קבע. In his own voice he grounds Rebbi Yehuda's requirement in תשבו כעין תדורו — ומ"מ לדעתו לדירת קבע הוא צריך ומטעם תשבו כעין תדורו — and concludes from it that the Tanna Kamma's reason is accordingly מתורת עראי. And in explaining Rebbi Zeira he fixes the area at which a dwelling becomes permanent: סוכה — הראויה מן הסתם היא ד' אמות על ד' אמות כשיעור קטן שבבתיים שבפחות מכן אינו קרוי בית — a space smaller than 4×4 amos is not called a בית at all.

What is not a בית is not קבע. In the Meiri's own construct, therefore, an area below 4×4 amos is עראי — and this is the identical criterion the Gemara assigns to the Rabbanan on 3b: אפילו רבנן מודו דאי אית ביה ארבע אמות על ארבע אמות דיירי ביה אינשי ואי לא לא דיירי ביה אינשי. where a sukkah smaller than 4×4 amos is permitted to them precisely because דדירת עראי. The Meiri's measurement and the Baraisa's are the same, arrived at from opposite directions — he from what makes a בית, the Gemara from what the Rabbanan permit in a sukkah.

As to the dimension of height, the Meiri brings a מפרשים יש who reads Rebbi Yehuda's קבע as satisfied by height itself — למעלה מכ' כשרה מכל צד שאי אפשר לה בלא קבע, ולמטה מכ' כשרה — a reading he reports without rejecting. He does reject a second מפרשים יש, under which Rebbi Yehuda would require no קבע at all, dismissing it with ואין הדברים נראין.

Both dimensions of קבע assigned to Rebbi Yehuda here are therefore present in the Meiri — the one in his own words, the other in a reading he preserves. And the עראי that mirrors them is not an inference from the Meiri but the Rabbanan's stated position in the Baraisa.



And this approach would be consistent with the Baraisa on 3b that a dwelling is considered to be a קבע if it is 4×4 amos or greater in length and width. Likewise, this is similar to Rebbe's opinion on 7b which defines the קבע of a sukkah solely in the terms of length and width at 4×4 amos or greater. Therefore, the difference between the two Tannaim is that Rebbi Yehuda utilizes height **or length and width** in defining a דירת קבע.

Furthermore, this is consistent with how the Ritva and Ran understand the Gemara's use of the term כולו סבירא להו, which they understand to mean that each disputant disagrees with his fellow in some aspect of the halacha.

This conclusion is further supported by the fact that Rebbi Yehuda can be seen to dispute R' Shimon's קבע requirement for a fourth wall in that he agrees with Mishna 2a that states: ושאין לה שלשה דפנות ... פסולה. Therefore, a sukkah that has three walls is valid.

Likewise, Rebbi Yehuda can be shown to oppose Rabban Gamliel's understanding of the קבע requirement of a sukkah in that it cannot be a mobile sukkah, such as one that sits atop a wagon. This is observed in Gemara 23a which states that Rebbi Yehuda's reason for


invalidating a sukkah built on the back of an animal is based on the verse that states: **הג** **הסוכות תעשה לך שבעת ימים**, the festival of Succos you shall make for seven days. Rabbi Yehuda does not invalidate the sukkah because it is a mobile sukkah, rather because a sukkah atop an animal is rabbinically forbidden to be used in such a manner on the day of Yom Tov and consequently cannot be utilized for all seven days. The implication is that the Gemara understands that had it not been for the one day of Yom Tov, Rabbi Yehuda would allow a sukkah to be built on the back of an animal. Therefore, Rabbi Yehuda would permit a sukkah to be built on top of a wagon since its use would not be forbidden on Yom Tov and could be used for all seven days.

Furthermore, while Rabbi Yehuda allows a sukkah to be built at 4×4 amos or greater in length to qualify as a **דירת קבע**, in accordance with the understanding of the Ritvah and Ran, Rabbi Yehuda disputes Rebbe's absolute minimum requirement of 4×4 amos when he validates a sukkah of less than that measurement. This is clearly seen on 2b where in the name of Rav, Rav Huna and Rav Chanan bar Rabbah state that the argument between the Tanna Kamma and Rabbi Yehuda is in a sukkah above 20 amos in height which is less than 4×4 amos in length and width.

(End.)

Why does Rav Huna in the name of Rav state that the dispute between the Tanna Kamma and Rabbi Yehuda in a sukkah above 20 amos is at exactly 4x4 amos rather than 4×4 amos and less?

The reason for this is that a shade ratio of 1:5 (length to height) is a diagonal line reaching 20 amos in height at exactly 4×4 amos. This means that if the dispute between the Tanna Kamma and Rabbi Yehuda was stated as being at 4×4 amos **and less** the reader would have thought that if the sukkah was merely 20 amos in height or lower it would be valid according to the opinions of the Tanna Kamma and Rabbi Yehuda. But this is not the case for either of their opinions.



Regarding the Tanna Kamma's opinion, examples can be found of how a sukkah such as one that is 2×2 amos can be no higher than 10 amos in height and one of 3×3 amos can be no higher than 15 amos in height. And regarding Rabbi Yehuda's opinion of the קבע of a sukkah, Rabbi Yehuda invalidates a temporary sukkah which is built less than 4×4 amos in length and which is at the same time 20 amos or lower in height. Therefore, the dispute must be described as being at **exactly** 4×4 amos. However, both the Tanna Kamma and Rabbi Yehuda permit a sukkah which is built at less than 4×4 amos.

(End.)

In the name of Rav, Rav Huna and Rav Chanan bar Rabbah argue over a matter of length on 2b, but what is the source of their dispute?

The Gemara on 22b states that when Mishna 2a says *פסולה מצלתה* it means that equal or greater shade of the s'chach must be present at the ground level where a person dwells, otherwise the sukkah is invalid. This is the opinion of all regarding the ס"פ of Mishna 2a and not a unique requirement of Rabbi Zeira on 2a or Rav Huna on 2b.

מטערה - לארץ שאין מחילה בפחות מטערה: הא' ו' וזו בהו"ך מטערים אפילו העליונה כמורה לשפת עשרים והתחתונה לשפת עשרה ק"א סלקא דעסק דמאשר אלמא אמרין חבוס רמי בפחות מרובע טפח: תריץ הכי כלומר חוץ דקאמר פחות מג' הוא ובלבד דקמי הכי קאמר ובלבד שלא תהא עליונה ט': כלן מלמעלה כלן מלמטה: הא דדייקין כי תריץ פסולה למעלה קאי: כשיש בין קנה לקנה כמלא קנה אפילו אין חוס לשם	אבל שלשה כיון דלית ביה טפח לא אמרין חבוס רמי: ושצילתה מרובה מרובתה בשרה: הא כי תרדי פסולה והא תנן באיך פירקין *ושחמתה מרובה מצילתה פסולה הא כי תרדי כשרה לא קשא' כאן מלמעלה כאן מלמטה אמר רב פפא היינו דאמרי אינשי כוזא מלעיל כאיסתרא מלחתה: מעובה כמין בית: תרדי' המעובה כמין בית אע"פ שאין הכוכבים נראין מתוכה כשרה אין כוכבי הנה נראין מתוכה בית שמאי פוסלין ובית הלל מכשירין:	שאלו בגובהן שלשה כיון דקורה רחבה משה אפילו בגובה שלשה נמי אמרין חבוס רמי ויש למד דלא דמי דכלא כדי תיקשי לן הכס כלאו טעמא דחבוס רמי ליתכשר האי מבי כיון דלן הקורה למעלה מטערים אלא הייט עממא כדאמרין הכס דבעין קורה על גבי מבוי ואפילו הכי קורה משום מחילה בעין איכר קנה ולא משיב דבר כלל אלא א"ס ק' אי בפך שלשה כי הוהא דהכס דהמח מנחין ואפילו כמין לטותל:
--	--	---

Therefore, we can deduce that an additional factor involved in the disputes between Rabbi Yehuda and the Tanna Kamma according to Rav Huna and Rav Chanan bar Rabbah, is not that the s'chach must be capable of producing shade at the floor of the sukkah where a person dwells (regarding this everyone agrees), but more specifically regarding the amount of time that the s'chach (and not the walls) must provide protection from the daytime heat in order for the sukkah to be valid, as the Torah states: **וְסוּכָה תְהִיָּה לְצֵל יוֹמָם מִחֹרֶב**.


Imagine a person in a very hot desert. He needs protection from the daytime heat. Would a structure with a length to height ratio that provides only 5 minutes of shade at the floor of the sukkah where a person dwells to be valid.

The Gemara on 2b explains that the Tanna Kamma of Rav Huna in the name of Rav understands that the source of the 20 amos height limitation of a sukkah is derived **directly** from the requirement that a sukkah must provide a certain amount of protective shade during the daytime heat, which according to him is minimally accomplished with a length to height ratio of 1:5, as the Gemara states: **כמאן כרבי זירא דאמר משום צל הוא וכיון דרויחא איכא צל סוכה**.


However, Rav Chanan bar Rabbah's opinion also holds that a valid sukkah must provide equal or more shade at the ground level where a person dwells as described in Gemara 22b

and Mishna 2a, but he does not hold that the 20 amos height limitation of a sukkah is derived from the requirement of shade, as does Rav Huna. Rather, the 20 amos height limitation of a sukkah is derived from the law of noticeability (למען ידעו), like Rabbah stated on 2a.

Consequently, this opinion of the Tanna Kamma did not have an answer for what the minimum amount of time is that a sukkah had to provide shade from the daytime heat. Therefore, the Tanna Kamma of Rav Chanan bar Rabbah's opinion utilized the principle of תפשת מרובה לא תפשת מועט תפשת and determined the shade ratio from their understanding of the minimum size sukkah. And since this opinion of the Tanna Kamma holds that a sukkah is valid until 20 amos in height on the basis of למען ידעו and Beis Shammai's opinion that a sukkah is a דירת קבע, which requires a minimum size sukkah of ראשו ורובו ושולחנו in regards to its length, it used these factors to define its opinion of what the minimum amount of time is that a legal sukkah must provide shade during the daytime heat.



Therefore, Rav Huna maintained that a valid sukkah required 1 hour and 31 minutes of shade from the s'chach at the floor of the sukkah (1:30:29, rounded up, as a shiur may only be rounded to stringency), while Rav Chanan bar Rabbah maintained that the minimum amount of shade from the s'chach is 27 minutes (0:26:48, likewise rounded up).



Pythagorean Theorem:

$$a^2 + b^2 = c^2$$

$$\begin{aligned} 20^2 + 4^2 &= c^2 \\ 400 + 16 &= c^2 \\ \sqrt{416} &= c \\ 20.396078054371 &= c \end{aligned}$$

Arcsin Formula:

$$angle = \arcsin\left(\frac{a}{c}\right)$$

$$\begin{aligned} \arcsin\left(\frac{20}{20.396078054371}\right) \\ \arcsin(0.98058067569092) \\ = 1.3734 \text{ rad} = 78.69^\circ \end{aligned}$$

Angles of a Triangle:

$$a + b + c = 180^\circ$$

$$\begin{aligned} 78.69^\circ + 78.69^\circ + c &= 180^\circ \\ 157.38^\circ + c &= 180^\circ \\ c &= 180^\circ - 157.38^\circ \\ c &= 22.62^\circ \end{aligned}$$

(End.)

Why does the Gemara state on 2b that Rav Chanan bar Rabbah's opinion in the name of Rav is not like one of the three Amoraim?

Rav Chanan bar Rabbah's opinion **is not like the three** Amoraim (Rabbah, Rabbi Zeira, and Rava) who attempt to explain the 20 amos height limitation of a sukkah. His use of תפשת מועט תפשת מרובה לא תפשת תפשת מועט תפשת is coming to establish the Tanna Kamma's opinion regarding the minimum amount of time that a sukkah must provide equal or more shade from the s'chach at the floor of the sukkah where a person dwells. And, through deduction it can be determined that Rav Chanan bar Rabbah's opinion regarding the 20 amos height limitation of a sukkah is in accord with Rabbah, למען ידעו. In fact, from the perspective of Rav Chanan bar Rabbah's opinion, Rabbi Yoshiyah's dictum regarding the 20 amos height limitation of a sukkah and his dictum regarding the minimum amount of time that a sukkah must provide equal or more shade from the s'chach, represents a single opinion of the Tanna Kamma. Therefore, Rav Chanan bar Rabbah's dictum is entirely dependent on Rabbi Yoshiyah's dictum being correct.

And the simplest reason why למען ידעו is the only logical option as Rav Chanan bar Rabbah's source for the 20 amos height limitation, is that he disputes Rav Huna at 4×4 amos, who is in accord with Rabbi Zeira, and Rava's opinion of temporariness in regard to the dimension of height does not permit a sukkah to be over 20 amos. However, a more nuanced and complicated answer at this stage is that since Rav Chanan bar Rabbah's opinion is based on Beis Shammai's understanding that a sukkah is a דירת קבע requiring ראשו ורובו ושולחנו, he cannot at the same time hold that a sukkah is a דירת עראי like Rava who will be found later to be in accord with Beis Hillel.

The proof that this is the correct understanding of the Gemara is that after Rabbi Yehuda's Baraisa regarding Queen Helene sukkah refutes Rabbi Yoshiyah's dictum regarding the requirement that the walls must reach the s'chach, Rav Chanan bar Rabbah's opinion is no longer addressed by the Gemara afterward. This is because the Gemara understands that Rav Chanan bar Rabbah's opinion is dependent on Rabbi Yoshiyah's source of למען ידעו being correct.

(End.)

If Rav Chanan bar Rabbah agrees with R' Yoshiyah that the source for the 20 amos height limitation of sukkah is למען ידעו, why does the Gemara on 2b state that R' Yoshiyah argues with Rav Chanan bar Rabbah because he gives a measurement of length?

This is because there is more than one factor that effects the height of a sukkah, as the Gemara on 2a previously stated: מיהו סוכה דנפישין מיליה. While Rav Chanan bar Rabbah and R' Yoshiyah agree that the source for the 20 amos height limitation of sukkah is למען ידעו, R' Yoshiyah still argues with Rav Chanan bar Rabbah over the nature of the קבע needed for a valid sukkah, the definition of which also impacts the height of a sukkah. Rav Chanan bar Rabbah's measurement of length represents his opinion that the קבע of a sukkah is in accordance with Beis Shammai, ראשו ורובו ושולחנו. This becomes the basis upon which he determines the minimum amount of time that the s'chach of the roof must be capable of producing shade at the floor of the sukkah, as the Gemara on 22b explains regarding the סיפא of Mishna 2a that states: ושחמתה מרובה מצלתה פסולה. Therefore, Rav Chanan bar Rabbah establishes a minimum shade ratio using the principle of תפשת מרובה לא תפשת תפשת based on the 20 amos height limitation of למען ידעו and Beis Shammai's opinion that a sukkah is a קבע דירת, which requires a minimum size sukkah of ראשו ורובו ושולחנו in length to accommodate a person's table, 7b.

Whereas R' Yoshiyah maintains that the קבע of a sukkah is that in addition to the roof, the sukkah's walls must also provide shade when the sun is at diagonal to the sukkah. Because of this he understands that there is no minimum amount of time that the s'chach must provide shade at the floor of the sukkah, as the Baraisa on 7b states: ושחמתה מרובה מצלתה פסולה. Therefore, R' Yoshiyah argues with Rav Chanan bar Rabbah (and Rav Huna) in maintaining that a sukkah must provide shade for the entire day and not just for a certain amount of time during the daytime heat of the afternoon. Consequently, he holds that there is no universal height-limiting shade ratio and so long as the walls reach the s'chach the sukkah can extend far above 20 amos unimpeded.

How does Rav Huna and Rav Chanan bar Rabbah's opinions accomplish equal or greater shade at the floor of the sukkah in accordance with Gemara 22b and Mishna 2a in a sukkah above 20 amos in height?

Given that the mitzvah of dwelling in a sukkah applies around the world, in both the Northern and Southern hemispheres at the same time during Yom Tov of Sukkot, the Tanna Kamma understood that the physical dimensions of a sukkah were determined on the basis of the sun passing over the sukkah at a perpendicular angle of 90-degrees. This would account for locations where a person is dwelling in exile, and the sunlight and heat of the day is the most direct and intense. The fact that this shade ratio and its resulting physical dimensions will produce less to even no shade time of the s'chach at the floor level in other locations of the world (such as Israel, Russia, or Australia) is not a concern.

Therefore, just as we are not concerned about the angle of the sun and the lack of shade of the s'chach produced at sunrise or at nighttime, so too the Torah is not concerned that this sukkah with its physical dimensions may be placed in locations of the world that do not experience the sun at a direct 90-degree angle and produce the same amount of shade from the s'chach.

(End.)

What is Rabbi Yehuda's opinion regarding the minimum amount of shade time when he allows a sukkah to be as high as 40 or 50 amos?

As previously stated, the Ritva and Ran cite a tradition of the Geonim that the phrase כולוהו סבירא להו, as used in Gemara 7b, indicates that the Tannaim disagree as to the nature of the קבע of a sukkah. Therefore, Rabbi Yehuda disputes Beis Shammai's opinion that the קבע of a sukkah requires a person to bring his physical table inside the sukkah, which drives a minimum size sukkah of ראושו ורובו ושולחנו. Consequently, since Rabbi Yehuda does not require a table, he holds that the minimum size sukkah is ראושו ורובו. And since Rabbi Yehuda's opinion is that a sukkah is a דירת קבע on the basis of an abstract dimension without limit above 20 amos, he does not and cannot utilize the principle of תפשת מרובה לא תפשת to determine the proper amount of shade time. Rather, he holds that a sukkah needs only to provide proper shade at הצות for a singular moment when the sun is at a 90-degree angle to the sukkah.

And Rabbi Yehuda informs us that this is the correct understanding of his opinion by stating in his Baraisa regarding Queen Helene's sukkah in 2b, סוכה שהיא גבוהה למעלה מעשרים אמה. אמה פסולה ורבי יהודה מכשיר עד ארבעים וחמשים אמה. He states עד ארבעים וחמשים אמה to indicate that even at ראושו ורובו (one amah in length for the measurement of a person, 8a), a sukkah could be ארבעים or חמשים amos in height, which indicates that he does not hold by a ratio at all. Otherwise, he could not state either or.

ראשו ורובו וסלחו : ימא כהכר סוכה • בלרסה וברכה פליגי דחזויהו לית לה דכי פליגי רבנן בסוכה המלומדת בשיעור הכשר אורך סוכה פליגי ובמשי מיהא מכשר לפניו היא גבוהה דמין דרומחא לוחא לל סכך או טעמא אחרינא להכשריה דרכ הונא סכך אי אפשר להעמיד מחלוקתן בפסוקה מד' אמות דאם כן כלא גבוהה מעשרים אמה פסולה	ורובו ושולחנו פליגי אבל יותר מראשו ורובו ושולחנו דיה כשרה ומר סבר מראשו ורובו ושולחנו עד ד' אמות פליגי אבל יותר מר' אמות דברי הכל כשרה מיתבי סוכה שהיא גבוהה למעלה מעשרים אמה פסולה ורבי יהודה מכשיר עד ארבעים וחמשים אמה אמר רבי יהודה *מעשה בדילני המלכה בלוד שהיתה סוכתה גבוהה מעשרים אמה ודיו זקנים נכנסין ויוצאין לשם ולא אמרו	הכל היתה חמשים כשרה ארבעים מיבעיא כדדיוקין כריש אלמנה מיוגית (כחוטות דף נה.) גבי אלמנה ששהתה שמים ושלש שנים ולא חכמה מוטתיה איבדה מוטתיה ובסוף כ"ק (דף קתה) גבי ליקחון מן הדעוים ארבע וחמש לאן ארבע וחמש גזיון דהסם מיתא דהיו זו ואין לריך לומר זו משום הכי קשיא ליה אבל קשיא מההיא דפרק צטת שמים (נהג' לנ')
--	--	---

Furthermore, he provided a רמז to his opinion that there is no shade ratio **and** that the minimum size sukkah is ראושו ורובו with the use of the numbers 40 and 50. Because the numerical value of 1 amah (ראשו ורובו), 40 amos, and 50 amos is 91, the gematria of סוכה.

(End.)

[illegible]

Rebbi Abba said to Rav Shmuel bar Yitzchak: **כמאן כב"ש**. According to whom are you ruling? According to Beis Shammai? But we pasken like Beis Hillel! (And what is Beis Hillel's opinion? Baraisa 3a: **אפילו אינה מחזקת אלא ראשו ורובו כשרה**.)

41 | Page

Furthermore, since Rav Huna's opinion maintains that a sukkah can be built at less than 4×4 amos, the Tanna Kamma can no longer pasken like Rebbe who maintains that a sukkah is a דירת קבע, which requires a minimum size sukkah of 4×4 amos. Consequently, if Rav Huna's opinion represents the Tanna Kamma of Mishna 2a, the halacha for the minimum size sukkah must be decided in accordance with Beis Shammai that a sukkah is a דירת קבע which requires a person to bring his table into his sukkah in order to dwell in the manner that he normally does in his house all year long, 28b and 7b.

Finally, in regards to Rav Shmuel bar Yitzchak's understanding of the dispute between Beis Shammai and Beis Hillel, which he understood in the terms of a דאורייתא requirement that a sukkah must be either a דירת קבע or דירת עראי, the Gemara adds that it was said by some that the exchange continued with R' Abba asking, "who is it that told you" that Beis Shammai and Beis Hillel argue over a דאורייתא as to whether a sukkah is a דירת עראי or דירת קבע? And Rav Shmuel bar Yitzchak responded to Rabbi Abba, "it is Beis Shammai" that told me!

42 | Page

What is the meaning and significance of Rav Nachman bar Yitzchak's challenge to Rav Shmuel bar Yitzchak?

[illegible]

Rav Nachman bar Yitzchak is challenging Rav Shmuel bar Yitzchak's understanding that the argument between Beis Shammai and Beis Hillel over the minimum size of a sukkah, is originating from a דאורייתא requirement. As such, a דאורייתא perspective of the argument represents a Torah requirement by Beis Shammai that a sukkah must be large enough to accommodate a person's table and by Beis Hillel that a sukkah cannot be above 20 amos in height. And since Beis Hillel's understanding of a דירת עראי is in the terms of the height of a sukkah, which does not involve a table, they can validate a minimum size sukkah regarding the dimension of length as small as ראשו ורובו. Therefore, they argue in a small sukkah over a דאורייתא as to whether a sukkah is a דירת עראי or a דירת קבע.

Rav Nachman bar Yitzchak's assertion that their argument could possibly be over the manner in which one eats, which could even take place in a large sukkah, is an attempt to establish the argument as regarding a דרבנן. This would mean that the argument in the sukkah is not defined in terms of a דאורייתא requirement, that a sukkah must either be a דירת קבע or דירת עראי with their resulting minimum size sukkahs. In doing so, Rav Nachman bar Yitzchak is stating that the Tanna Kamma who argues with Rabbi Yehuda in Queen Helene's sukkah according to Rav Huna's opinion and permits a sukkah to be higher than 20 amos when larger than 4x4 amos on the basis of a 1:5 shade ratio, would not have to pasken in accordance with Beis Shammai that the minimum size sukkah is ראשו ורובו. Rather, if the argument between Beis Shammai and Beis Hillel is over a דרבנן regarding the manner in which a person eats from a table (whether in a large or small sukkah) that would mean that the Tanna Kamma can still pasken according to Beis Hillel in regards to a minimum size sukkah of ראשו ורובו because it wouldn't matter anymore that Rav Huna permits a sukkah higher than 20 amos when beyond 4x4 amos in length.

(End.)

How do we know that the Gemara concluded that Beis Shammai and Beis Hillel are in fact arguing in a small sukkah over a דאורייתא requirement as to whether a sukkah is a דירת עראי or דירת קבע?

ותניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחכ"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי אלא לאו ש"מ הא ב"ש הא ב"ה

מהארי: אלא לא גרסינן וכו' גרסינן
לשולחן כדמצינן פליגי: פסוק מן
המזוזה - סלה מפרש סעמא לקח:
ואינו נחלש - אלא פודה לשולחן
ויואל ביוכל אם לא נאלו כשאר קרקע
בלא בנין: משורכי המלמזה - מי
האם אשר בנה בית חדש וגו'
(דמצינן ב') ואין מערבין ב' - דרך
בתיים להיות פתוחין לחצר וארבעה
בתיים פתוחים לחצר אחת וכן ויולין
דרך חצר לרשות הרבים נמלא החצר
כשולחן לשולחן כל אחד מיוחד
לדמיא דאחיה ויחמיה אבא אבא

מיבעי ליה ובסוכה קמנה לא פליגי והתניא
מחזקת ראשו ורובו ושולחנו כשרה רבי אומר
עד שיהא בה ארבע אמות על ארבע אמות
והניא אידך רבי אומר "כל סוכה שאין בה
ארבע אמות על ארבע אמות פסולה וחכ"א
אפילו אינה מחזקת אלא ראשו ורובו כשרה
ואילו שולחנו לא קתני קשיין אהדדי אלא
לאו ש"מ הא ב"ש הא ב"ה אמר רב ונפריא
מתניתין נמי דיקא מרקינן ב"ש פוסלין וב"ה
מבשרין ואם איתא כש"א לא יצא רב"ה
אמרם יצא מיבעי ליה ואלא כשיא מי

ושלחן בסוכה מילתא
קשיין קשיין ודמצינן
ב' ואפיקנא חלמנא
דמצינן שחמא פוסלין
ראשו ורובו ושולחנו
ואם ליה ר' אבא מי תא
וא"ר רב הונא ב"ש תא
אלא הוה פסולת ואפיקנא
פסולת פסולת ודמצינן
ב"ש וב"ה בסוכה קמנה
ותניא רבי אומר כל סוכה
שאין בה ארבע אמות על
ארבע אמות פסולה וחכ"א
אפילו אינה מחזקת אלא
ראשו ורובו כשרה ואילו
שולחנו לא קתני קשיין
אהדדי אלא לאו ש"מ הא
ב"ש הא ב"ה אמר רב ונפריא
מתניתין נמי דיקא מרקינן
ב"ש פוסלין וב"ה מבשרין
ואם איתא כש"א לא יצא
רב"ה אמרם יצא מיבעי ליה
ואלא כשיא מי

The proof that the Gemara rejected Rav Nachman bar Yitzchak's challenge that Beis Shammai and Beis Hillel are arguing in a small sukkah over a דרבנן regarding the manner in which a person eats, is that after stating the Baraisa on 3a: רבי אומר כל סוכה שאין בה ארבע אמות, the Gemara concludes with the statement: ואילו שולחנו לא קתני. Meaning, that since the Gemara finds Beis Hillel arguing over the minimum size sukkah of ראשו ורובו with Rebbe who holds that the minimum size sukkah is 4x4 amos, and it is clearly not over the manner in which one eats from a table, the Gemara deduces that Beis Hillel does in fact maintain that the minimum size sukkah originates from a דאורייתא requirement that a sukkah is a דירת עראי, just as shall be learned from the Baraisa on 3b regarding the laws of houses, that the Rabbanan can build a sukkah at less than Rebbe's 4x4 amos because they also hold that a sukkah is a דירת עראי in accordance with Beis Hillel.

אליבא דרב הונא דנמנא ולחיה
לשחיתא דמצינן קרקע ארבע אמות
ואין קשיין יוסף ומאיה ולרבעים
ולחיה אמה ושליש אמה בין שמי
עיריות והוא שישור שני קרפיות
שעכשו מנעקף בית זה לנרפן דעכשו
לית ביה ארבע אמות לא תשיב והוי
כמאל דליקא ואין העיריות מתחברות
בין לרב הונא בין לחיה בר רב אבי
מה לו להכריע שתי עיירות הוי ליה

ואין עושין אורו עיבור בין שתי עיריות ואין
דאזין והשוחטין רחלקן בו לימא רבי היא
ולא רבנן אפילו תימא רבנן עד כאן לא
קאמרי רבנן *התם אלא לענין סוכה דדירת
עראי היא אבל לגבי בית דדירת קבע היא
אפי' רבנן מודו דאי אית ביה ד' אמות על ד'
אמות דיירי ביה אינשי ואי לא לא דיירי ביה
אינשי: אמר רב פסוק מן המזוזה ומן

בסוכה דמצינן קרקע ארבע אמות
ואין קשיין יוסף ומאיה ולרבעים
ולחיה אמה ושליש אמה בין שמי
עיריות והוא שישור שני קרפיות
שעכשו מנעקף בית זה לנרפן דעכשו
לית ביה ארבע אמות לא תשיב והוי
כמאל דליקא ואין העיריות מתחברות
בין לרב הונא בין לחיה בר רב אבי
מה לו להכריע שתי עיירות הוי ליה

בסוכה דמצינן קרקע ארבע אמות
ואין קשיין יוסף ומאיה ולרבעים
ולחיה אמה ושליש אמה בין שמי
עיריות והוא שישור שני קרפיות
שעכשו מנעקף בית זה לנרפן דעכשו
לית ביה ארבע אמות לא תשיב והוי
כמאל דליקא ואין העיריות מתחברות
בין לרב הונא בין לחיה בר רב אבי
מה לו להכריע שתי עיירות הוי ליה

The Gemara then brings an additional proof with Mar Zutra who states that if the proper understanding of the argument was as Rav Nachman bar Yitzchak suggests, that Beis Shammai and Beis Hillel are arguing over a דרבנן regarding the manner in which a person eats, the Mishna should have concluded that Beis Shammai holds that a person does not discharge his obligation and Beis Hillel holds he does discharge, בש"א לא יצא וב"ה אומרים, יצא.

לא תזוז סוכה ואקשין על פסולת ב"ש וב"ה בסוכה קטנה התן פי שורה ראש ורובי בסוכה ושלחנו בתוך הבית בית שמאי פוסלין וב"ה מכשירין והייקת סוטה ונתת ב"ה מכשירין אצל שאת מחוקק אלו ראשו ורובו גבוה וב"ש פוסלין * בסוכה קטנה פליגי וב"ה דיימב אפסא רסלללללללללללל בתוך העוקבא	אמרו לו וקני כ"ש ח"כ היות סוכה כל יומך לא קיימת מלכות סוכה כל יומך ומסקינן סתם דהלכה כרבי יומך תחורגי דהס"א פלוגתא בסוכה גדולה דמסקינן דבתרתי פליגי בההיא הלכה כב"ה אבל הכא בסוכה קטנה ובהא הלכה כב"ש מיהו שמעתי דהס"א תימיה סיכי דייק מונה דעשה כב"ש לא עשה ולא כלום דראה דמיימי בעשה כב"ה מיימי	ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחוקקת אלא ראשו ורובו כשורה ואילו שולחנו לא קתני קשיין אהרדי אלא לאו ש"מ הא ב"ש הא ב"ה אמר מר זוטרא מתניתין גמי דיקא מדקתני כ"ש פוסלין וב"ה מכשירין ואם איתא בש"א לא יצא וב"ה אומרים יצא מיבעי ליה ואלא קשיא פי שהיה לעולם בתרתי פליגי פליגי בסוכה קטנה ופליגי בסוכה גדולה וחמורי מחמורא	פוסל פ"ב) בלא בנין : משוררי המלחמה : מי האש אשר בנה בית חדש וגו' (דברים כ) : ואין מערבין ט' דרך בתיים להיות פתוחין לחצר והכנה בתיים פתוחים לחצר אחת וכן יולאין דרך חצר לרשות הרבים נמצא החצר רשות לטען והבתיים כל אחד מיוחד לבעליו ואמרו חכמים אין מולאין חדשות לחדשות בלא עירוב שיערב כל חדשות לחדשות רשות אחת
--	--	---	--

Instead, the Mishna states ב"ש פוסלין וב"ה מכשירין which indicates that Beis Shammai holds that the sukkah itself is invalid according to the Torah, while Beis Hillel maintains that it is valid. Therefore, since they do argue over the structural validity of a minimum size sukkah, they are arguing over a דאורייתא requirement. And, as such the Gemara rejects Rav Nachman bar Yitzchak's challenge that the argument is over a דרבנן and cannot escape the halachic difficulty that Rav Shmuel bar Yitzchak has highlighted.

And this was the purpose of the Gemara stating on 2a, ומאי שנא, גבי מביי דתני תקנתא סוכה דאורייתא תני פסולה. The principle of פסולה taught there only becomes relevant here on 3a for the reader to understand the language of פוסלין in our Mishna that states: מי שהיה ראשו ורובו בסוכה ושולחנו בתוך הבית, בית שמאי פוסלין ובית הלל מכשירין. This sequence of thought was purposefully orchestrated to indicate here that the matter in dispute between Beis Shammai and Beis Hillel is regarding a דאורייתא, and not a דרבנן.

(End.)

What is the source of the dispute between Beis Shammai and Beis Hillel regarding the minimum size of a sukkah?

Mishna 28b states: עראי קבע וביתו עראי. כל שבעת הימים אדם עושה סוכתו קבע וביתו עראי. The Rabbanan further taught the Baraisa on 28b that states: כיצד ת"ר כל שבעת הימים אדם עושה סוכתו קבע וביתו עראי. היו לו כלים נאים מעלן לסוכה מצעות נאות מעלן לסוכה אוכל ושותה ומטייל בסוכה. Therefore, it can be deduced that according to the Rabbanan on 3b and Beis Hillel on 3a to make one's sukkah קבע and to transform his house into עראי, he needs only to אוכל ושותה ומטייל בסוכה, because in the end a person may not have elegant dishes or fine linens. And this requirement corresponds to Beis Hillel's minimum size sukkah of ראשו ורובו, that a person must be able to literally fit his head and most of his body inside the sukkah in order to be able to fulfill the requirement to אוכל ושותה ומטייל בסוכה.

[illegible]

However, Beis Shammai's opinion adds to the common denominator of ראו ורובו, in concluding that a person must literally pull his table out of his house, making his house אכיל ושותה (ראשו ורובו ושולחנו) in order for him to be considered a sukkah, עראי, and place the table inside his sukkah as he normally dwells in his house all year long. And the proof that Beis Shammai requires the table to be removed from his house is that Mishna 3a states: מי שהיה ראו ורובו בסוכה ושולחנו בתוך הבית ב"ש פוסלין ובית הלל מכשירין. Why does the Mishna state: ושולחנו בתוך הבית? Let the Mishna simply state that the table is outside the sukkah.

המחוקק ראהו ורזו וטולטו כשרה
 וטאזנה מחוקק אלא כדי ראהו ורזו
 כ"ס פוסקים מ' אחר מר וטולט
 דיקא גמי דכקנה פלגי ובקשוראל
 דפסקין ומתקנין כמך פקדן אפס
 מהדי: אלא לא גרסין וסב גרסין
 טולט מהדי פלגי: פקדן מן
 כהנא: ומהדי טולט אלא: בטות יב.
 פקדן טו.
 פקדן יז.

Regarding the requirement to make one's sukkah קבע, what are the rationales of the Tannaim? In 28b, all hold that the Torah requires us to "תשבו" (dwell) in a permanent manner in a sukkah. Therefore, a sukkah must be a "dwelling" and not like other structures, such as a hut to merely sleep in or a watchtower from which to stand guard. Rebbe holds that a sukkah needs to be a permanent dwelling like a house, which if built less than 4×4 amos will lose its ability to be a dwelling, similar to the Baraisa on 3b which explains regarding houses: דאי אית ביה ד' אמות על ד' אמות דיירי ביה אינשי ואי לא לא דיירי ביה אינשי. Whereas Beis Shammai holds that the unique feature of a dwelling is that a person eats meals at a table, otherwise it is not a dwelling but more like a hut, watchtower or some other type of structure. However, Beis Hillel holds that if a person simply sat in the sukkah and ate their meals without a table it is enough to make it a valid dwelling, even without a physical aspect of קבע that would make it a דירת קבע structurally in a physical sense, as is found by the opinions of the Tannaim on 7b.

Therefore, the argument between Rebbe, Rabbi Yehuda, Beis Shammai and Beis Hillel is regarding the nature of קבע that constitutes a dwelling within which one can fulfill the commandment to "תשבו". Beis Hillel uniquely makes his sukkah קבע through simply eating his meals in the sukkah as opposed to his house, while at the same time maintaining that the physical structure of a sukkah requires a דירת עראי based on the words שבעת ימים, like Rava transmits to us on 2a.

(End.)

After discussing the dispute between Beis Shammai and Beis Hillel, why does the Gemara ask the reader on 3a to identify the author of the Baraisa on 3b regarding a house that is less than 4×4 amos?

מאן תנא להא דתנו רבנן בית שאן בו ארבע אמות על ארבע אמות פטור מן המזוזה ומן המעקה ואינו מטמא בנגעים ואינו נחלט בבתי ערי חומה ואין חוזרין עליו מעורכי המלחמה ואין מערבין בו ואין משתתפין בו ואין מניחין בו עירובואין עושין אותו עיבור בין שתי עיירות ואין האחין והשותפין חולקין בו **לימא רבי היא** ולא רבנן אפילו תימא רבנן עד כאן לא קאמרי רבנן התם אלא לענין סוכה דדירת עראי היא אבל לגבי בית דדירת קבע הוא אפי' רבנן מודו דאי אית ביה ד' אמות על ד' אמות דיירי ביה אינשי ואי לא לא דיירי ביה אינשי

(בשבתנו) פי' שהיה
 ראש ורבו ולא קני
 פי' שהיה בשבת שאנה
 שוקק אלא ראש
 ורבו ודחתו כמבאר
 (משום) דקניא ל'
 א"ח א"ח שבת
 גדולה והא דכשרי' פ'
 נטותם יושב על פ'
 השבת ושלחו בדרך
 בדיקת פלגי' א' הכי
 ר' יצא י"ל שבת היה
 חל קצת אלא מדרגתי
 מילין ש"ס כמות
 קטנה פלגי' ואשרי' א'
 הכי רבשבת קטנה
 פלגי' יצאו פי' שהיה

עשה ולא כלום וציל דלעפערך ההם
לחיותי איבער דביים ממזמרים מדרבנך
ובינך מוקדם לה דלדורייא ואל
דבוקין אים עשה כדברי ב"ש לא ולא
ידי חובתו אלא ידורייא כדלשכתך
לביס איבער דרביב אלא דמלכות
דגזרי שמה ימך אחר שולח וקאמרי
לא קיימת משה סוכה מימך דלדור
מלדורייא לא קיים ומדביים שמה
שמה לביס: **בית** שאלן צו ד'
אמר: צירשמי תביס שאלן סוכל
התם: וצו ועוד אלא ליה למימר

וב"ה אמרים יצא ושאינה מחזקת אלא כד
ואשו וחבו בלבד ב"ש פוסלין ובית הלל
מבשרין מאן תנא ללא דתו רבנן בית
שאן בו ארבע אמות על ארבע אמות
יפסד מן המזוזה יומן המעקה יאינו ממלא
בנגעים יאינו נחלם בבתי ערי חומה ואין
תחורן עליו מעורכי המלחמה ואין מערבין
בו ואין משתתפין בו ואין מניחין בו עירוב
ואין

בחדות הבתים וגמשים טום כליו
 דרין בלחות בית וכל הבתים דירה
 אחת ואשמועין האל דבית שאין זו
 ד' על ד' אין לךד ליתן את הפה :
 אין מהתקין בו שתיקטו הכתים
 על כל חצר האצחזה למנוי כדך
 שתיקטו עירוב לבתי האצר שיה
 טהנין בשיתוף ואם בית קמן זה
 פתוח לחצר שבמבטי ואין בית
 אחר פתוח לה אין מהתקין בו
 אין לרעה ליתן בשיתוף : ואין
 מענין בו עירוב - חסד לחצר

מסורת
השם

סוכה פרק ראשון סוכה

6 עין משפט
נר מצודה

(non 35)

ואין ענין אותו מיידר בין שתי מיררות : דאן נחשבת מיררות (97)
(מ.) טעמן קרפף לשתי מיררות אס יס לזו שבפנים אמה ושיריים ולזו
שבפנים אמה ושיריים עושה קרפף לשיריים להיות אחת שתי מיררות
המבולטות זו מזו קרפף אחת ושתי זו בצלמא וזו נמצא אותו בית
המבולטות : וכן שבפנים אמה ד' מפרסות לשחוקן
נעשה אותו בית כעמידה לזן בלשה
עובדה עשרים וטולס ומחצית
ליות עשרות בלשה לזן בלשה חסן
שזו עשרות לזן : אחת וטולס
אלפים מחצית לזן : ואס יס בית
פחות מ' אחת ארס חשוב לזרס :
ואין אחת : האסותן עולקן : ז.
קצ' בלשה שתי יטולס לזן : וס
אס ז' חלקל לפי שאלן ז' בלז
וכי לזס : לזס מ' ד' : אס : וזל
חשוב סוכה בלז מ' : אחת : וזל
רזן : ד' : וזל : חסן : בסוכה

[illegible][illegible]

Since Beis Shammai and Beis Hillel were proven by the Gemara to be arguing in a small and large sukkah over a דאורייתא, Rav Shmuel bar Yitzchak's logical argument remains


standing that the halacha of a minimum size sukkah must be according to Beis Shammai, ראשו ורובו ושולחנו.

Therefore, as an alternative to Beis Shammai's opinion the Gemara now suggests that perhaps Rebbe is the author of the Baraisa on 3b regarding a house that is less than 4×4 amos, and not the Rabbanan. In doing so, the Gemara is stating that if the Rabbanan are teaching Rebbe's Baraisa about houses perhaps they should also follow his opinion regarding sukkahs. Consequently, the Gemara is suggesting to reject Rav Huna's **opinion of קבע**, which is Beis Shammai's requirement of ראשו ורובו ושולחנו and instead adopt Rabbi Zeira's understanding of the dispute between the Tanna Kamma and Rabbi Yehuda on 2a and who holds according to Rebbe's minimum size sukkah of 4×4 amos.

What is the practical difference and how do we know Rabbi Zeira held according to Rebbe's opinion in regard to the קבע of a sukkah? Both Rabbi Zeira and Rav Huna hold that the 20 amos height limitation of a sukkah has its source in a 1:5 shade ratio, as the Gemara on 2b states that the two opinions are similar in that they both identify the source of the 20 amos height limitation of a sukkah as originating from this shade ratio. However, in regard to the קבע of a sukkah Rav Huna maintains that a sukkah can be less than 4×4 amos and even as small as ראשו ורובו ושולחנו, like Beis Shammai. Whereas Rabbi Zeira maintains that a person sits in the shade of a sukkah until 20 amos. How is this possible with a 1:5 shade ratio, since a person can see that a sukkah of 2×2 amos can only be as high as 10 amos and one of 3×3 amos can only be as high as 15 amos in height. In truth it is not possible. Rather, a person is able to sit in the shade of the sukkah until 20 amos because Rabbi Zeira holds in accordance with Rebbe's understanding of קבע and maintains that a valid sukkah requires a minimum of 4×4 amos.

אמר רבה אמר קרא למען ידעו רבינו חננאל
 סוכה שהיא גבוהה
 מעשרים אמה פחותה
 וזו ידעתה פחותה
 וחנן עירובין פ"ב
 שורא גובה מעשרים
 אמה יפנים פ"ט פ"ב
 דקתני תקנתא כלאחר
 יפנים זה העובד יוריד
 מעשרים אמה אין אדם יודע שורר בסוכה
 משום דלא שלמא בה עינא רבי זירא אמר
 מהבא "וסוכה תהיה לצל יומם מחורב עד
 עשרים אמה אדם יושב בצל סוכה למעלה
 מעשרים אמה אין אדם יושב בצל סוכה
 אלא בצל דפנות אל אביי אלא מעתה
 חננאל בדוריינתה נמי • שיך גמיר
 תקנתא: סוכה דנפשי מילתה • ואין
 דומין תקנותיהן זו לזו ואריך לשטת
 הלשון לכל תקנה ותקנה טעון בגובהה
 יתעס וכשאינה גבוהה יגביה וקאין
 לה שלש דפנות יעקה לה ותחתיה
 מרובה יוסף סבך הלכך פסיק ותני

רבי זירא אמר מהבא: "וסוכה תהיה לצל יומם מחורב", עד עשרים אמה אדם יושב בצל סוכה, למעלה מעשרים אמה — אין אדם יושב בצל סוכה אלא בצל דפנות.



However, at this point the Gemara continues with adding another alternative to Beis Shammai by stating the opinion of the Rabbanan in context of Baraisa 3b: אפילו תימא רבנן: עד כאן לא קאמרי רבנן התם אלא לענין סוכה דדירת עראי. In doing so the Gemara conspicuously leaves the question regarding the identity of the unknown author of the Baraisa on 3b unanswered and in front of the reader. This has also led the reader to understand that the Rabbanan actually hold that a sukkah is a דירת עראי in accordance with Beis Hillel and consequently that they hold that the minimum size sukkah is ראשו ורובו. This is understood from the Gemara previously stating that Beis Hillel validates a sukkah at less than Rebbe's 4×4 amos on 3a.

עוד שיהא בה ארבע אמות על ארבע אמות ותניא אידיך רבי אומר "כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה ורביא אפילו אינה מרוקת אלא ראשו ורובו כשרה ואילו שולחנו לא קחני קשין אהרדי אלא לאו ש"מ הא ב"ש הא ב"ה אמר מר וזמרא מרעיתין נמי דיקא מרדקתני ב"ש פוסלין וב"ה

ראשו ורובו שולחנו
ואמר ר' זעורא פני תא
וא"ר ר' זעורא ב"ש חזא
לא חזא ס"נה ואקשינן
על פסא דחולקת
ב"ש וכו' בסנה קמטת
וחתן פי שניה ראשו
ורובו בסנה שולחנו
בתוך הבית בית שש
פוסלין וב"ה פסלין
דייק סנה חזא ב"ה

אמר ר' זעורא פני תא
וא"ר ר' זעורא ב"ש חזא
לא חזא ס"נה ואקשינן
על פסא דחולקת
ב"ש וכו' בסנה קמטת
וחתן פי שניה ראשו
ורובו בסנה שולחנו
בתוך הבית בית שש
פוסלין וב"ה פסלין
דייק סנה חזא ב"ה

עוד שיהא בה ארבע אמות על ארבע אמות ותניא אידיך רבי אומר "כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה ורביא אפילו אינה מרוקת אלא ראשו ורובו כשרה ואילו שולחנו לא קחני קשין אהרדי אלא לאו ש"מ הא ב"ש הא ב"ה אמר מר וזמרא מרעיתין נמי דיקא מרדקתני ב"ש פוסלין וב"ה

ואינו נחלט - אלא שיהא לעולם
ויולא כיוכל אם לא נאלץ כשאר קרקע
כלא בנין: משורכי המלחמה - מי
האין אשר בנה בית חדש וגו'
(דגריס ב'): ואין מערבין צו - דרך
בניהם להיות פחותין לחצר וסוכה
בתיים פחותים לחצר אחת וכן יולאין
דודי חזא לרבות דהיה נחלט חזא



(End.)

What are the logical consequences of the Gemara revealing on 3b that the Rabbanan maintain that a sukkah is a דירת עראי in accordance with Beis Hillel as described on 3a, when the Gemara interprets the Baraisa regarding a house that is less than 4×4 amos according to the Rabbanan's perspective?


Until here the reader only understood a דירת עראי in terms of **the height** of a sukkah in accordance with the initial explanation of Rava on 2a. However, the Gemara explained on 3b that the reason it cannot ascribe with certainty the authorship of the Baraisa regarding a house that is less than 4×4 amos to Rebbe, is because the Rabbanan could also have authored the Baraisa since they maintain that a sukkah built in an area which is less than 4×4 amos in regards to **the dimensions of length and width** is also considered a דירת עראי.

[illegible]

Therefore, just as Rebbi Yehuda holds that a sukkah is a דירת קבע which can be satisfied by being either higher than 20 amos in height or 4×4 amos or greater in length and width, the Rabbanan hold to the opposite that a sukkah is a דירת עראי which can be satisfied by being either 20 amos or lower in height or less than 4×4 amos in length and width, **regardless of its height**. Therefore, it can be concluded that Rebbi Yehuda and the Rabbanan both agree to the dimensions of קבע and עראי but only disagreed as to whether a sukkah is a דירת קבע or a דירת עראי from the words תשבו שבעת ימים and תשבו שבעת ימים in the verse בסוכות תשבו שבעת ימים. This is because 4×4 amos is itself the very threshold of a permanent dwelling, so that an area of less than 4×4 confers the quality of עראי irrespective of height, as the Baraisa on 3b establishes: דאי אית ביה ד' אמות על ד' אמות דיירי ביה אינשי ואי לא לא דיירי ביה אינשי — if it has 4×4 amos people dwell in it permanently, and if not, they do not. For the Rabbanan, a floor space too small to be dwelt in permanently is not made a permanent dwelling by its height, and its smallness area fixes it as עראי at every height.



And, the proof that Rabbanan hold that a sukkah is a דירת עראי on the basis of height **or length and width**, is that there is no way that they can maintain the concept of a דירת עראי according to the initial understanding of Rava's opinion on Sukkah 2a and not be refuted by Rabbi Yehuda's Baraisa regarding Queen Helene's sukkah which was over 20 amos in height while the Elders were silent. Rather, it should be understood on 2a that Rava was only coming to explain the Mishna's statement regarding the limitation of a sukkah in regard to the dimension of height specifically, but his explanation of a דירת עראי in regards to the dimension of length and width would be different and also in accord with Beis Hillel on 3a.



נשנים כדמתי פליגי : פקור מן המזוזה • טלה מפרש טעמא לקמן : חזי נחלג • אלא פודה לעולם ויולא ביוכל אם לא נאלו כשאר קרקע בלא בנין : משורתי המלחמה • מי האיש אשר בנה בית חדש וגו' (דמית כ) : ואלן מערבין זו • דרך נביהם להיות פתוחין לחצר והדנה בחים פתוחים לחצר אחת וכן וולאין דרך חצר לרשות הדנים נמלא החצר דמית לולא נהיהם על ארבע

דבוסה מעשה כרבי יוחנן החורדי שחלה והלט וקני כ"ט וקני צ"ה לבקרו ומלואיה שניה יוסב רלשו ורובו כבוסה ושולחט בתוך הבית אמרו לו וקני כ"ט ח"כ היית טוב כל יומך לא קיימת מלש טובה כל יומך ומסקין חסם דהלכה כרבי יוחנן החורדי דהאיא פלוגמח כבוסה גדולה דמסקין דכדמתי פליגי כהאיא הלכה כצ"ה אבל הכא כבוסה

מחזקת ראשו ורובו ושולחנו כשרהרבי אומר עד שיהא בה ארבע אמות על ארבע אמות ורביא איך רבי אומר "כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה ורביא אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אחרדי אלא לאו ש"מ הא ב"ש הא ב"ה אמר מר זוטרא מתניתין נמי דיקא מדקתני ב"ש פוסלין ובי"ה מבשרין ואם איתא בשי"א לא יצא ובי"ה

כ"ה ואסקינא חלמחא צדיכא שרתא סחוקת ראשו ורובו ושולחנו ואמר ליה ר' אבא פני חא וא"ר רב חננא ב"ש חיא ולא חזו סתה ואקשינן עלה פטאי דחאקת ב"ש ובי"ה כבוסה קפנה דהפן מי שרית ראשו ורובו כבוסה ורובו בתוך הבית בית שפאל פוסלין ובי"ה מבשרין • וייקת סתה ונתח ב"ה מבשרין אפ"ל שותת

Therefore, it must be concluded that the opinion of Rav Huna in the name Rav, in which the Tanna Kamma disputes Rabbi Yehuda at exactly 4×4 amos, is the opinion of Beis Shammai, as the Gemara 3a states: איכא דאמרי אמר רבי אבא דאמר לך מני א"ל ב"ש היא ולא תזוזי. This is because beyond 4×4 amos and over 20 amos in height is a completely permanent dimension where the Rabbanan could not hold that a sukkah is a דירת עראי in either height or length and width in accordance with Beis Hillel. And, since Rav Huna's opinion also allows a sukkah to be less than 20 amos in height and as small as ראשו ורובו, it is in a completely temporary dimension in regard to the dimensions of height and length and width, which Rebbe and Rabbi Yehuda dispute. Therefore, Rav Huna's dictum in the name of Rav is transmitting Beis Shammai's understanding of the 20 amos height limitation of a sukkah in accordance with צל and that the קבע of a sukkah requires one's table.

Furthermore, the Gemara taught us to understand the proper questions to ask and how to extrapolate a more complete understanding of the Gemara. Given Rabbi Yehuda's Baraisa regarding Queen Helene's sukkah on 2b, and the understanding that the Rabbanan hold in accordance with the opinion of Beis Hillel, that a sukkah is a דירת עראי on the basis of either height or length and width (meaning that a sukkah can only be above 20 amos in height when it is built less than 4×4 amos in length), the reader should ask: "Is it the way of a queen to dwell in a small sukkah?" The Gemara has already taught us the answer: אמר רב. אשי לא נצרכה אלא לקיטוניות שבה. Therefore, as opposed to Beis Shammai who disputes Rabbi Yehuda and maintains that her sons were sitting in the large sukkah which was over 20 amos high, the Rabbanan hold to the opposite according to Beis Hillel that a sukkah is a דירת עראי and maintain that Queen Helene was sitting in the small sukkah of less than 4×4 amos for privacy and her sons were sitting with her. Therefore, the Elders did not say a word to her about her sukkah being over 20 amos in height.

Furthermore, the opinion of Rav Huna in name the of Rav (which represents Beis Shammai's opinion), the opinion of the Rabbanan (which represents the opinion of Beis Hillel), and the opinion of Rabbi Zeira (which represents the opinion of Rebbe), all argue with Rabbi Yehuda from different points of the dispute. And a רמז that the Gemara would come to prove that there were multiple opinions of dispute after having properly defined a דירת עראי and דירת קבע, is that the Gemara on 3a stated: רבנן סברי בניה בסוכה מעליא הווי יתבי. It should have stated בסוכה גדולה to reflect Rav Huna's dictum in the name of Rav. However, since Beis Shammai, Beis Hillel, and Rebbe's opinions all argued with Rabbi Yehuda the Gemara states בסוכה מעליא to accommodate all of the disputes.

Therefore, in conclusion since Queen Helene's sukkah's walls did not reach the s'chach and the Elders did not say a word to her, it disproves R' Yoshiyah's dictum in the name of Rav which is in accord with Rabbah who states למען ידעו is the source for the 20 amos height limitation of a sukkah. In addition, since Rav Chanan bar Rabbah's dictum in the

name of Rav is based on למען ידעו being correct, his calculation for a required shade ratio on the basis of the principle of תפשת מועט תפשת מרובה is also refuted.

However, according to Rabbi Zeira who maintains that a sukkah requires a 1:5 shade ratio and is a דירת קבע in accordance with Rabbi's opinion, he held that her sons were sitting in the large sukkah that was greater than 4×4 amos and over 20 amos in height. Therefore, the Elders did not say a word to her. While Rabbi Yehuda maintained that her sons sitting in her private sukkah which was exactly 4×4 amos while over 20 amos in height.

But regarding Rav Huna in name the of Rav, who maintains that a sukkah requires a 1:5 shade ratio and is a דירת קבע in accordance with Beis Shammai's opinion, the Gemara states that the Rabbanan held that her sons were sitting in the large sukkah that was greater than 4×4 amos and over 20 amos in height. Therefore, the Elders did not say a word to her about her sukkah being over 20 amos. While Rabbi Yehuda maintained that her sons were sitting in the small sukkah which was 4×4 amos or less while above 20 amos in height.

Finally, according to the Rabbanan who maintain that a sukkah is a דירת עראי in accordance Beis Hillel, they held that Queen Helene was sitting inside a small sukkah of less than 4×4 amos which was higher than 20 amos in height and her sons were sitting with her. Therefore, the Elders did not say a word to her. And according to them, Rabbi Yehuda maintained that her sons were sitting in the large sukkah which was 4×4 amos or greater while above 20 amos in height.

(End.)

A Preemptive Reply

How should we understand the solution offered by the תוספות רי"ד and ריטבא who conceptualize Queen Helene's sukkah as being comprised of two sections with differing heights to explain how the Rabbanan maintained their opinion that a sukkah is a דירת עראי?

The problem that the תוספות רי"ד and the ריטב"א are seeking to address is that a preliminary reading of Rava on 2a (that a sukkah above 20 amos is invalid) is defeated by Rabbi Yehuda's Baraisa regarding Queen Helene's sukkah, which was גבוהה מעשרים אמה and went unobjected to by the Elders. Therefore, to harmonize Rabbi Yehuda's Baraisa with the Mishna in a way that sustains the Rabbanan's position as the Tanna Kamma in opposition to Rabbi Yehuda, a fact was inferred from outside the Gemara's words. The תוספות רי"ד and the ריטב"א propose that Queen Helene's sukkah must have contained two rooms of differing heights — one above twenty amos and one below — and that her sons were sitting in the lower room. This lower sukkah is a fact not mentioned in the Baraisa or Gemara elsewhere. It was a necessary inference because no other solution was available to prevent the refutation of our understanding of Rava by Rabbi Yehuda's Baraisa.

However, in accordance with the methods stated at the beginning of this work, the Talmud's own language is preferred over an inference not present in the Baraisa. The broader context and subsequent discussions of the Gemara portray a more nuanced understanding of the dispute between Rabbi Yehuda and Rava – between קבע and עראי. This is understood when the Gemara develops a series of deductions that reveal that Rava's opinion that a sukkah is a דירת עראי is derived from Beis Hillel and that Beis Hillel's understanding of a דירת עראי includes the dimension of length and width, not just the dimension of height. The Gemara establishes this in several crucial steps.

First, it utilized on 3a Rabbi Yehuda's dispute with Rav Huna's 1:5 shade ratio in Queen Helene's sukkah as context to define the functional difference between Beis Shammai's opinion that a sukkah is a דירת קבע and Beis Hillel's opinion that a sukkah is a דירת עראי. The Gemara's deductive reasoning in this context effectively connects Beis Hillel and Rava's opinions that a sukkah is a דירת עראי. This is accomplished because Rav Huna's opinion, that a sukkah can be higher than 20 amos in height when beyond 4x4 amos in length, invalidates their common understanding of a דירת עראי. Through this mechanism the Gemara shows that Rava's opinion is derived from Beis Hillel's.

Next, the Gemara continues on 3a proving that Beis Shammai and Beis Hillel are not arguing in a sukkah over a דרבנן regarding the manner in which a person eats, as Rav Nachman bar Yitzchak challenged. In the process the Gemara further defined Beis Hillel's concept of a דירת עראי as one that includes more than just the dimension of height. Beis Hillel's concept of a דירת עראי is understood to also include the dimension of length and

width when he argues with Rebbe over the minimum length and width of a sukkah. This is clearly seen on 3a when the Gemara states: ותניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וכ"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי אלא לאו ש"מ הא ב"ש הא ב"ה

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

Finally, the Gemara associates the Rabbanan's opinion with Beis Hillel and Rava's opinion using the Baraisa on 3b regarding the laws of houses when it states that the Rabbanan could also have authored the Baraisa because they can build a sukkah at less than Rebbe's 4×4 amos. This is because they maintain that a sukkah is a דירת עראי in accordance with Beis Hillel on 3a and by extension Rava on 2a. Therefore, Beis Hillel and Rabbanan hold that a sukkah can also acquire the quality of עראי by being built at less than 4×4 amos in length and width as opposed to having to be built at 20 amos or less in height.

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

והתניא אידך רבי אומר כל סוכה שאין בה ארבע אמות על ארבע אמות פסולה וחב"א אפילו אינה מחזקת אלא ראשו ורובו כשרה ואילו שולחנו לא קתני קשיין אהדדי לאו ש"מ הא ב"ש הא ב"ה

עד כאן לא קאמרי רבנן התם: But prior to this point, where does the Gemara speak about a sukkah being a דירת עראי after Rava introduces the concept, except on 3a where Beis Hillel argues with Beis Shammai over a דאורייתא involving the dimension of height in the case of Queen Helene's sukkah and where Beis Hillel argues with Rebbe over the dimension of length and width.


Furthermore, this was the thrust of what Rabbi Abba said to Rav Shmuel bar Yitzchak on 3a when he stated: כבית שמאי, כמאן?! But the Rabbanan pasken like Beis Hillel!


והא"ר לא אמר לה דבר *אמר רב שמואל בר יצחק *הלכה צריכה שתהא מחזקת ראשו ורובו ושולחנו *אל רבי אבא כמאן כב"ש א"ל אלא כמאן איכא דאמר אבא רבי אבא דאמר לך מני א"ל ב"ש היא ולא תוון מינה מתקיף לה רב נחמן בר יצחק

והא"ר לא אמר לה דבר *אמר רב שמואל בר יצחק *הלכה צריכה שתהא מחזקת ראשו ורובו ושולחנו *אל רבי אבא כמאן כב"ש א"ל אלא כמאן איכא דאמר אבא רבי אבא דאמר לך מני א"ל ב"ש היא ולא תוון מינה מתקיף לה רב נחמן בר יצחק

והא"ר לא אמר לה דבר *אמר רב שמואל בר יצחק *הלכה צריכה שתהא מחזקת ראשו ורובו ושולחנו *אל רבי אבא כמאן כב"ש א"ל אלא כמאן איכא דאמר אבא רבי אבא דאמר לך מני א"ל ב"ש היא ולא תוון מינה מתקיף לה רב נחמן בר יצחק

Therefore, just as Rabbi Yehuda holds that a sukkah is a דירת קבע which can be satisfied by being either higher than 20 amos in height or 4x4 amos or greater in length and width, the Rabbanan hold to the opposite that a sukkah is a דירת עראי which can be satisfied by being either 20 amos or lower in height **or** less than 4x4 amos in length and width, **regardless of its height.**





This is because 4×4 amos is itself the very threshold of a permanent dwelling, so that a length and width of less than 4×4 confers the quality of עראי irrespective of height, as the Baraisa on 3b establishes: דאי אית ביה ד' אמות על ד' אמות דיירי ביה אינשי ואי לא לא דיירי ביה אינשי — if it has to it 4×4 amos people dwell in it permanently, and if not, they do not. For the Rabbanan, a floor space that is too small to be dwelt in permanently, it cannot be made a permanent dwelling by its height, and its small area fixes it as עראי דירת at every height. And conversely, Rebbe does not invalidate a sukkah of 4×4 amos or greater when it is built 20 amos or less in height — he treats it as a קבע דירת on the dimension of length and width.

In conclusion, after the Gemara establishes that Rava's opinion that a sukkah is a דירת עראי is derived from Beis Hillel and that Beis Hillel's understanding of a דירת עראי includes the dimension of length and width, the reader can understand both the deeper nature of the dispute and how the Rabbanan, Beis Hillel, and by extension Rava, avoid refutation by Rabbi Yehuda's Baraisa regarding Queen Helene's sukkah. The queen sat in her private sukkah of less than 4×4 amos, with her sons beside her. And since the sukkah is a דירת עראי by the dimension of length and width it is valid for the Rabbanan even though it exceeds 20 amos in height.

This resolution does not require the inference of a second lower sukkah proposed by the תוספות רי"ד and the ריטב"א; the Talmud's own language carries it without altering the understanding of the Baraisa.

(End.)

If the Rabbanan who hold that a sukkah is a דירת עראי allow a sukkah to be above 20 amos why does the Gemara on 3b discuss the need to reduce its size with various materials implying that a sukkah above 20 amos is invalid?

Analyzing this Gemara in context of Beis Hillel's opinion, when does such a case like this ever occur? The Gemara can only be discussing a sukkah that was built 4×4 amos or larger and over 20 amos in height, making it a דירת קבע. Therefore, the Rabbanan who maintain that a sukkah is a דירת עראי in accordance with Beis Hillel, state that if one came **to reduce its height, as opposed to its length**, it must be done with the right materials and intentions. The purpose of this Gemara is to address how to make a correction to the floor of a sukkah when such a case occurs.

החגג לנידון סבתים הוא נהיה טולס כדריס בבית אחד הלך בעין בית הדלוי לדירה ושיטוף המבוי אזט אלא לגרף החגרות והגרות לאו דירה מיטו ואלקך לא בעי דירה אלא באוירא של חגג דיו ובמקום משתמר ויהיו כל החגרות טולס כאילו משמשן להיות אחד: מי	מילי בית דלמדוי קאי יהבינא ליה חצר האי דלמיסטר קאי לא יהבינן ליה חצר: יהיתה גבוהה מעשרים אמה ובא למעשה בכרים ובסחכות לא הוי מיעוט ואע"ג	וכ"ש סחכות מ"ו: שקי עיירות דהוא הדין עיר ובים אזט אגב דנקט ר"מ עיר נקטי רבנן שקי עיירות דהא לחייא בר רב דאגרי קרפף אחד לשתייהן על כרחך לא נקטי רבנן שתי עיירות דווקא דהוא הדין עיר ובים דע"י טרגגין המובלעים בחוץ שבשים אמה וקריים הולך כדמוכח פירק עושין משחמר ויהיו כל החגרות טולס כאילו משמשן להיות אחד: מי
--	--	---

(End.)

This is also the case in which the sukkah is 4×4 amos or larger. Therefore, if the portion of the s'chach that produces enough shade is above 20 amos in height, the sukkah cannot be considered a valid דירת עראי. Therefore, the purpose of this Gemara is to address how to make a correction to the ceiling of a sukkah when such a case occurs.

(End.)

If so, what is the dispute between the Tanna Kamma and Rabbi Yehuda regarding a sukkah atop another sukkah in Mishna 9b?

Mishna 9b states: סוכה על גבי סוכה העליונה כשרה והתחתונה פסולה ר' יהודה אומר אם אין דיורין – A sukkah atop another sukkah, the upper one is valid and the lower one is invalid. Rabbi Yehuda says: If there are no tenants in the upper one, the lower one is valid.

סוכות השנים	סוכה פרק ראשון סוכה	18 עין משפט נר מצוה
מתני' כאלו עשאה בתוך הבית . ופסולה כדמציא בבביתא בגמ' : התחתונה פסולה . דמי סכין יס לה וקרא פסול סוכה תחת סוכה כדלקמן : אם אין דיורין . בגמרא מפיש לה : גמ' למה לי למחזי כאלו עשאה בתוך הבית . מהאז קרא דנפקא לן תוך הבית נפקא תורה אור לן תחת האילן ולמה לי למחזי האז בהאך : הא קא ממערף סכך פסול . מחזיר סכך פסול הוא דמחזיר (דגריס זו) באספק מנרקד ומיקבד מזהה שאלה מאסף מנרקד עשה סוכתך בפסולת גורן כגון קצין ובפסולת יקב כגון אשכולות ויקניות ומזירות אלא תלוש בעין ומחזי לל האילן ללל הסכך להשלים לללה	ר' קא ממערף סכך פסול כהר סכך כזר . לפי שהאילן מחזיר ובעין דבר תלוש דומיא דפסולת גורן ויקב ואם הסוכה שחת האילן מאוכסת מרזי שאלה מרובה מתחתה לאז מיסתבר שתפסל ממוס ירחף סכך פסול כיון דמי שקלא ליה לפסול אחזי ללה מרובה אלא כשאין ללה מרובה אלא מחמת הפסול חזי והא דלא משני כגון דבלא פסול ללה מרובה ממוס דאז מוז למימרא דהשתא נמי דמשני בשחבתן קא פריך מוז למימרא ותדע דגבי מקרה סוכה בשפורין או בחרושת המטה מכשירין לקמן (דף פו.) בשם ריזח בעיניה כמותן ואע"ג דלא מחזי כה	גמ' א ב ג מ"ה פ"ט חולסת סוכה סוכה יב סג עשין פג עור ש"ס א"ח ט"י מרזח סכך ה' : ס רח מ"ה טס סוכה כב סג טז ח"ט א"ח ט"י מרזח סכך ה' : רבינו הגנאל לשמה : בתנא' הושיה המקור חתם הגאון ר' שמשון

The Gemara on 9b presents Rabbi Yermiya's Baraisa about composite s'chach configurations. The Gemara subsequently focuses on the obvious unanswered question regarding Rabbi Yermiya's first example which results in two valid s'chachs — how much vertical separation between the upper and lower s'chachs is required before the upper s'chach invalidates the lower as a sukkah above a sukkah? On 10a, Rav Huna states one tefach, while Rav Chisda requires four tefachim. For them, the top layer of s'chach with these small gaps form a temporary shelter that suffices to disqualify the lower sukkah.

However, since Shmuel does not ascribe to the concept that a temporary shelter nullifies a fixed shelter as seen further down on 10b, he introduces a different principle of כהכשרה כך כהכשרה — as the sukkah's validation so is its invalidation. For Shmuel, Rabbi Yermiya's top layer of s'chach must be at least ten tefachim high to invalidate the lower sukkah.

The Gemara then tests Shmuel's principle of כהכשרה כך כהכשרה verses Rav Huna and Rav Chisda by mapping these three opinions onto the Tannaitic dispute with Rabbi Yehuda in the Mishna on 9b. As such, if Rabbi Yehuda shares Shmuel's principle of כהכשרה כך כהכשרה, then if the top sukkah is less than ten tefachim and the Tanna Kamma maintains that upper sukkah is valid while the lower sukkah is invalid, it would indicate that the Tanna Kamma

holds like either Rav Huna or Rav Chisda who maintain that a small gap between the s'chachs invalidates the lower sukkah.

However, the Gemara then brings Rav Dimi from the West to explain the dispute differently where the Tanna Kamma and Rabbi Yehuda both subscribe to the principle of כהכשרה כך פסולה, like Shmuel. Accordingly, the dispute in Mishna 9b is not related to the ten tefachim height requirement, regarding this both the Tanna Kamma and Rabbi Yehuda agree. Rather the argument is over the requirement for a person to have had an intention for the mitzvah when building a sukkah — כהכשרה כך פסולה. And Rabbi Yehuda's operative test for determining if there was intent for the upper space to serve as a valid sukkah is if the lower sukkah's s'chach can firmly support two persons and their bedding.

תלמוד בבלי סנהדרין פרק ט"ז הלכה ט"ז
 בעליונה התחתונה כשרה מאי אין דיוורין
 אילימא דיוורין ממש אמר דיוורין קא גרמי
 אלא לאו מאי אין דיוורין כל שאינה ראויה
 לדירה ודוכי דמי דלא גבוה עשרה מכלל דתנא קמא
 ראויה לדירה פסולה כי אתא רב דימי אמר במערבא 'אם אין התחתונה
 יכולה לקבל ברים וכסתות של עליונה התחתונה כשרה מכלל דתנא קמא
 סבר אע"פ שאינה ראויה לקבל פסולה איכא בינייהו דיכולה לקבל על
 ידי הדרק: מותני' פירס עליה סדין מפני הרמה או תחתיה מפני הגשר
 או שפירס ע"ג הקטוף פסולה אבל פירס הוא על גבי נקליט המטה :

תחתונה משום סוכה תחת סוכה :
 היך דתחתונה פסולה . משום סוכה
 תחת סוכה : וקיימא עליונה כחוד
 כ' . לנגה טל תחתונה דהוא קרקעיתא
 דעליונה : פשיטא . דכי חד מנייהו
 תחתיה תרובה לאו סוכה . תחת סוכה
 היא ומאי אשמעינן רבי ירמיה :
 תחתונה כשרה ועליונה פסולה
 אילמריכא ליה . כדקיימא עליונה
 כחוד כ' : מיד ניגזר . למיפסל

This is derived from the Mishna's use of the plural language "if there are no tenants in the upper one." Likewise, the Gemara uses of the word דיוורין and in describing Rav Dimi's bedding test it invokes the plural form of כרים וכסתות. This is critical for understanding the positions of both the Tanna Kamma and Rabbi Yehuda. Because this dispute is a continuation of the previous argument in Mishna 9a between Beis Shammai and Beis Hillel over whether a sukkah needs to be built with the mitzvah in mind in order to be considered a valid sukkah.

As such, for the Tanna Kamma who aligns with Beis Hillel and does not require intent, if the lower sukkah's s'chach barely supports two tenants with their pillows and blankets then by the same structural fact it would firmly support one and the upper space between the two s'chachs would be considered a valid sukkah, making the lower one invalid.

Whereas Rabbi Yehuda aligns with Beis Shammai and maintains that כהכשרה כך פסולה requires a person to have the intention to make the upper space a sukkah. Only then would it be capable of disqualifying the lower sukkah. This is learned from 9a where the Gemara associates Beis Shammai with Rabbi Eliezer on the basis of Rabbi Eliezer's strict reading of תעשה לך שבעת ימים. And Rabbi Yehuda also reads the same verse with the same strict

posture at Gemara 23a. Therefore, Rabbi Yehuda's requirement for intent in the case of a sukkah above a sukkah follows directly.

Given this, the Mishna's plural דיורין functions for Rabbi Yehuda as evidence of intent derived from the physical structure when there are no tenants present. He applies the principle of רוב מנהגן של בני אדם — that a person builds his sukkah for Yom Tov to firmly accommodate a minimum household, namely himself and his wife (28b, תשבו כעין תדורו). Therefore, an empty space between two layers of s'chach that would barely support two people is not a valid sukkah because it is physically inconsistent with the proper intent needed to create a valid sukkah. And since the majority of people do not plan to spend Yom Tov by themselves, Rabbi Yehuda considers the upper space as not intentionally built for the mitzvah and therefore invalid even when it has ten tefachim in height.

However, if even one tenant were present in the upper space and it only supports one person firmly, Rabbi Yehuda agrees with the Tanna Kamma that the upper space is a valid sukkah. The need for a proxy to determine intent from the physical structure is unnecessary because the tenant's actual use of the structure is direct evidence of intent that the upper space was built to serve as a sukkah. The plural threshold of Rabbi Yehuda's test applies only when no tenants are present. Therefore, when the space between two layers of s'chach is **not fit for tenancy and cannot firmly support two people with their pillows and blankets**, Rabbi Yehuda assumes the builder had no intention for that space to serve as a sukkah for Yom Tov. And this aligns with the Gemara's statement that it is not the tenants that cause the sukkah to be valid, but intent.

(End.)

If the Elders who visited Queen Helene permitted a sukkah to be above 20 amos when less than 4x4 amos in area, why does the Tanna Kamma of Mishna 2a state categorically that a sukkah above 20 amos is invalid?

The answer was clearly stated by the Gemara at the beginning on 2a: מיהו סוכה דנפישין מיליה — פסיק ותני פסולה. The details for lowering the s'chach of a sukkah are numerous therefore the Mishna taught it as a פסיק ותני despite the more nuanced understanding of the Elders and Beis Hillel. The Mishna chose the categorical פסיק ותני for simplicity, which when read in absolute terms obscures the details regarding the exception of a narrow sukkah of less than 4×4 amos that is also higher than 20 amos in height.

This approach to פסולה ותני פסיק is not the author's invention but the Gemara's own construction when it portrays the potential resolutions to the Mishna's statement: סוכה שהיא גבוהה למעלה מעשרים אמה — פסולה.

כמאן אזלא הא דאמר רבי יאשיה אמר רב: מחלוקת בשאין דפנות מגיעות לסכך, אבל דפנות מגיעות לסכך — אפילו למעלה מעשרים אמה כשרה. כמאן?

The Gemara asks: In accordance with whose opinion is that which Rabbi Yoshiya said that Rav said: The dispute between Rabbi Yehuda and the Rabbis with regard to the fitness of a *sukkah* more than 20 amos high is specifically in a case where the walls of the *sukkah* do not reach up to the roofing; however, in a case where the walls of the *sukkah* reach up to the roofing, the Rabbis concede that even if the roofing is **more than 20 amos high, it is fit**. In accordance with whose opinion is it? **Rabba**.

כמאן אזלא הא דאמר רב הונא אמר רב: מחלוקת בשאין בה אלא ארבע אמות על ארבע אמות, אבל יש בה יותר מארבע אמות על ארבע אמות — אפילו למעלה מעשרים אמה כשרה. כמאן?

The Gemara asks: In accordance with whose opinion is that which Rav Huna said that Rav said: The dispute between Rabbi Yehuda and the Rabbis with regard to the fitness of a *sukkah* more than 20 amos high is specifically in a case where there is not an area of four amos by four amos in the *sukkah*; however, in a case where there is an area of more than four amos by four amos in the *sukkah*, the Rabbis concede that even if the roofing is **more than 20 amos high, it is fit**. In accordance with whose opinion is it? **Rebbi Zeira**.

כמאן אזלא הא דאמר רב חנן בר רבה אמר רב: מחלוקת בשאינה מחזקת אלא כדי ראשו ורובו ושולחנו, אבל מחזקת יותר מכדי ראשו ורובו ושולחנו — אפילו למעלה מעשרים אמה כשרה.

The Gemara asks: In accordance with whose opinion is that which Rav Chanan bar Rabba said that Rav said: The dispute between Rabbi Yehuda and the Rabbis with regard to the

fitness of a *sukkah* more than twenty amos high is specifically in a case where the *sukkah* is only large enough to hold one's head, most of his body, and his table, as, if the *sukkah* were smaller, it would not qualify as a *sukkah*; however, in a case where it is sufficiently large to hold more than one's head, most of his body, and his table, even if it is **more than 20 amos high, it is fit.**

Finally, this d'var Torah argues that subsequent to the Mishna's introduction, the Gemara sets out to develop the reader's understanding of how Beis Hillel's opinion (and Rava's by extension) that a *sukkah* is a דירת עראי, also has a specific configuration which permits a *sukkah* higher than 20 amos even though — פסיק ותני פסולה.

(פשוט)